



CITY OF VINCENT

# PICKLE DISTRICT PLANNING FRAMEWORK

AUGUST 2023



SOBGA





## ACKNOWLEDGEMENT OF COUNTRY

The City of Vincent acknowledges the Traditional Owners of the land, the Whadjuk people of the Noongar nation and pay our respects to Elders past and present.

We recognise the unique and incomparable contribution the Whadjuk people have made and continue to make to our culture and in our community. We will continue to seek the input of the Traditional Owners.

The land on which we live, meet, and thrive as a community always was and always will be Noongar land.

# CONTENTS

01	POLICY	5
02	CONTEXT	8
03	WHERE DO WE WANT TO BE?	25
04	THE PRIVATE REALM - BUILT FORM	28
05	THE PUBLIC REALM - PLACE PLAN	49
06	APPENDICES	62

# HOW TO READ THIS DOCUMENT

The Pickle District Planning Framework (PDPF) is structured around five Key Focus Areas:

## 01 POLICY

Sets out the legislative requirements of the PDPF including the relevant delegations, related policies, procedures and supporting documentation.

Sets the Policy purpose, objectives, operation, scope and relevant definitions.

## 02 CONTEXT

Outlines where we are now in the Pickle District in relation to each of the Strategic Community Plan (SCP) Pillars: Enhanced Environment, Accessible City, Connected and Healthy Community, Thriving Places, Sensitive Design and Innovative and Accountable. As well as the results of the **stakeholder engagement** surrounding this.

## 03 WHERE DO WE WANT TO BE

Sets out the vision and objectives of the PDPF that respond to the data and consultation collected in the 'context' focus area.

## 04 THE PRIVATE REALM - BUILT FORM

This statutory provisions of this framework have been prepared to guide development within the private realm now and into the future. This framework is to be read in conjunction with Local Planning Scheme No. 2 (Scheme) and State Planning Policy 7.3 Residential Design Codes (R-Codes) Volumes 1 and 2.

## 05 THE PUBLIC REALM - PLACE PLAN

The place-based actions of this framework have been prepared to improve outcomes and amenity within the Public Realm and will be delivered through capital works, strategic projects, advocacy and collaboration with the community and private sector.

# HOW DO THE VISION, OBJECTIVES, PRIVATE REALM AND PUBLIC REALM RELATE?

## VISION

High level goal for the area.

## OBJECTIVES

Capture the major themes that will influence the future of the area.

## THE PRIVATE REALM - BUILT FORM

Captures how privately owned land will change in the future and the parameters around this.

## THE PUBLIC REALM - PLACE PLAN

Captures how public land will be improved and how this will be achieved.

# 01 POLICY

## 1.1 PRELIMINARY

### 1.1.1 INTRODUCTION

The City of Vincent (City) Strategic Community Plan (SCP) vision is, “In 2028, the City of Vincent is a leafy and vibrant 24 hour city, which is synonymous with quality design and sustainability. Its diverse population is supported in their innovative endeavours by a council that says YES!”

This is supported by the six strategic pillars of:

- Enhanced Environment
- Accessible City
- Connected and Healthy Community
- Thriving Places
- Sensitive Design
- Innovative and Accountable

The City’s Local Planning Strategy (Strategy) sets out the long-term planning direction for the City by considering and applying State and regional planning frameworks, and community sentiment. It provides the rationale for the zones and other provisions within the local government area.

Local Planning Scheme No. 2 (Scheme) supports the Strategy. Part 2 of the Scheme sets out the Local Planning Framework and outlines the zones, appropriate land uses, density codes and other land reserved for public purposes.

The City has taken a place based planning approach in preparing the Strategy to inform the Scheme. The key elements of the ‘place based’ approach to planning included the following:

- Planning to achieve a holistic view and integrated outcomes for an area.
- Creating sustainable outcomes specific to particular areas and their communities.
- Creating community commitment and capacity.
- Ensuring community and stakeholder involvement and ownership in the process.

The Strategy intends to and informs the preparation of local planning policies that are adopted pursuant to the Scheme, in particular the Precinct Policies for each of the place-based areas of Vincent.

### 1.1.2 POLICY DEVELOPMENT

The Pickle District Planning Framework is a precinct policy, and local planning policy that has been prepared under the provisions of Schedule 2, Part 2, Clause 4 of the *Planning and Development (Local Planning Schemes) Regulations 2015*.

### 1.1.3 RELEVANT DELEGATIONS

16.1.1 Determination of various applications for development approval under the City’s Local Planning Scheme.

### 1.1.4 PURPOSE

The purpose of this policy is to guide development within the public and private realms of the PDPF area.

### 1.1.5 RELATIONSHIP TO OTHER INSTRUMENTS

#### R-Codes VOLUME 1

Where there is an inconsistency between this policy and the R-Codes Volume 1, this policy prevails to the extent of any inconsistency.

As contemplated by Clause 7.3.1 of the R-Codes Volume 1, the Deemed-to-Comply criteria and Local Housing Objectives in this Policy replace or augment the equivalent Deemed-to-Comply and Design Principle provisions of the R-Codes Volume 1.

#### R-Codes VOLUME 2

Where there is an inconsistency between this policy and the R-Codes Volume 2, this policy prevails to the extent of any inconsistency.

The Acceptable Outcomes in this Policy augment or replace the Acceptable Outcomes in the R-Codes Volume 2

While addressing the Acceptable Outcomes is likely to achieve the Element Objectives and Policy Objectives, they are not deemed-to-comply standards and applicants will need to demonstrate that the Element Objectives and Policy Objectives are addressed, to the satisfaction of the City.

Development may satisfy these objectives by alternative means or solutions.

Clause 4.5 of this Policy summarises the relationship between specific design elements addressed in the Policy and the R-Codes Volume 2.

#### OTHER LOCAL PLANNING POLICIES

Where there is conflict between this policy and any other local planning policy of the City, this policy prevails to the extent of any inconsistency.



## 1.2 POLICY PROVISIONS

### 1.2.1 DEFINITIONS

<b>Active Frontage</b>	A ground floor space where there is visual and physical engagement between those in the street and those on the ground floors of buildings.
<b>Adjoining Property</b>	Any lot which shares a boundary or portion of a boundary with a lot on which there is a proposed residential development site or is separated from that lot by a right-of-way, vehicle access way, pedestrian access way, access leg of a battleaxe lot or the equivalent not more than 6m in width.
<b>Articulation</b>	Architectural composition in which elements and parts of the building are expressed logically, distinctly, and consistently, with clear joints. For the purposes of this Policy articulation refers to points within a dwelling that clearly distinguish one part of the dwelling from another, such as setback between the ground and upper floors and indentations or 'breaks' within building walls.
<b>Awning</b>	A roof like structure attached to a building to provide shelter.
<b>Building Height</b>	As per the R-Codes Volume 1.
<b>Canopy Coverage</b>	Land area covered by tree crowns (branches, leaves, and reproductive structures extending from the trunk or main stems) from trees located within the subject site, excluding any area that falls within an adjoining privately owned lot.
<b>Character</b>	The defining features of a place, including scale, materiality, style or repetition.
<b>Climate Moderation Devices</b>	A structure or element which provides suitable control of internal temperature and air conditions, but does not include air conditioners.
<b>Colonnade</b>	A sequence of columns, covered or open, free-standing or part of a building.
<b>Cultural Infrastructure</b>	The buildings, places, spaces, people and technology necessary for arts and cultural education, creation, production, engagement, collaboration, sharing and contribution. It includes Public Art Infrastructure, as referenced in the City's Percent for Art Policy.
<b>Dedicated Road</b>	A road which has been committed to public use in accordance with the <i>Land Administration Act 1997</i> .
<b>Deemed Provisions</b>	Schedule 2 of the Planning and Development (Local Planning Schemes) Regulations 2015.
<b>Deep Soil Area</b>	As per the R-Codes Volume 2.
<b>External Fixtures</b>	As per the R-Codes Volume 1.
<b>Fine Grain</b>	Detailed urban elements including: spacing of facades distinguishing uses; and detailed materials in a facade or streetscape.



<b>Landscaping</b>	As per the R-Codes with additional clarification on “any other such area approved of by the decision-maker as landscaped area” to be defined as: Landscaped areas which are available for the use and enjoyment of the occupants, can include common and/or private open areas and recreational areas but does not include covered portions of driveways, hard paved driveways and parking areas, open air porous parking areas and driveways, or green walls.
<b>Natural Ground Level</b>	As per the R-Codes Volume 1 and Volume 2.
<b>Permanent Structure</b>	Building or development which is not temporary and cannot be easily removed, this includes but is not limited to development with footings.
<b>Planting Area</b>	An area, with a minimum soil depth and dimension of 1m that supports growth of medium to large canopy trees.
<b>Podium</b>	The base of a building upon which taller (tower) elements are positioned.
<b>Primary Street</b>	As per the R-Codes.
<b>R-Codes Volume 1</b>	Refers to State Planning Policy 7.3: Residential Design Codes Volume 1 (as amended).
<b>R-Codes Volume 2</b>	Refers to State Planning Policy 7.3 Residential Design Codes Volume 2 - Apartments (as amended).
<b>Secondary Street</b>	As per the R-Codes Volume 1.
<b>Skillion Roof</b>	A mono-pitch roof form.
<b>Soft Landscaping</b>	An area with a minimum soil depth of 300mm that contains in-ground planting, excluding removable planter boxes/pots, artificial turf, green walls and porous paving areas.
<b>Solar Absorptance</b>	The proportion of incident solar radiation that is absorbed by an external surface when exposed to the sun.
<b>Stall Riser</b>	The material installed between the windowsill and the ground in a shop front window.
<b>Storey</b>	That portion of a building which is situated between the top of any floor and the top of the floor next above it and, if there is no floor above it, that portion between the top of the floor and the ceiling above it but excludes any portion of a building used solely for car parking that is at least 50 percent below ground level.
<b>Streetscape</b>	The collective elements that contribute to a street, including architectural styles, front yards, car parking structures and access, infrastructure, footpaths, signage, street trees and landscaping and fencing and front boundary treatment.
<b>Verandah</b>	As per the R-Codes Volume 1.
<b>Visible Light Transmission</b>	Light passing directly through glass.
<b>Visually permeable</b>	As per the R-Codes Volume 1 and Volume 2.

## 02 CONTEXT

The area of West Perth known as the Pickle District is home to a diverse mix of creative industries and the Pickle District, and acts as an arts hub for broader Vincent. Its character includes iconic businesses and industrial style buildings that contribute to its distinct sense of identity and are why it is like no other place.

The following section highlights what makes the Pickle District unique, and the opportunities for improvement.

### 2.1 BACKGROUND

The PDPF area is situated in between Leederville and Northbridge. The area is bounded by Loftus Street to the west, Newcastle Street to the north, the Mitchell Freeway to the east and the Graham Farmer Freeway to the south.

It is a creative precinct, home to new and diverse creative businesses including art galleries, artist and design studios, a boutique theatre, photographic studios and creative co-op working spaces.

The area forms part of Boorloo – Noongar land belonging to the Whadjuk people of the Noongar nation.

Geographically, the area sits within a chain of wetlands of practical and spiritual significance to the Whadjuk Noongar people. It was renamed Lake Sutherland by European colonists and later drained in the 1870s and repurposed as areas for market gardening to feed Perth's growing population.

Early businesses in the area included furniture manufacturers such as Sandover & Co Furniture Factory originally located at No. 485 Newcastle Street, and Bryants woodyard/fuel merchant located on Duke Street (now Old Aberdeen Place).

Inspiration for the name 'Pickle District' comes from the vinegar brewing and pickle jam manufacturing factories in the area, which operated from around 1912. These included R.H. Masikell and CO Ltd sauce, jam and pickle manufacturers, originally located on Golding Street, later moving to No. 567 Newcastle Street.


On adjacent Golding Street, Phillip Stevens started a vinegar brewery in 1920. From 1922 until at least the 1950's, No. 4 Golding Street was the home of the WA Vinegar Brewery Ltd which manufactured Flag and Safe brand vinegar products.

Construction of the Mitchell Freeway in the 1970s impacted significantly on the area, as did the decline in the domestic manufacturing sector.

West Perth including the Pickle District is now known for the historic light industrial buildings and warehouse character. The area is transforming as the buildings are repurposed with new and diverse businesses and arts organisations.



Vinegar and pickling factories operated in the area in the 1900s, inspiring the name 'The Pickle District'. Credit: SLWA



The construction of the Mitchell Fwy in the early 1970s saw the demolition of residences in Simpson Street, two of which still remain today. Credit: Andrew Kailis



## 2.1.1 PRECINCT BOUNDARY

The PDPF boundary includes the northern side of Newcastle Street, and is bound by Loftus Street, the Graham Farmer Freeway and Charles Street.

The inclusion of the northern side of Newcastle Street in the boundary creates a buffer between the residential development to the north, and the high density development that is envisaged on the southern side of Newcastle Street.

Newcastle Street, up until Loftus Street, is included within the Free Transit Zone. Including this area within the PDPF supports the improvement of the public realm and encourages use of the service.

The Leederville Precinct Structure Plan area, which includes the Leederville Town Centre, is west of the PDPF area. Loftus Street is a major road and impacts accessibility between the two areas.



### LEGEND

- Precinct boundary
- Free transit zone
- 400m radius
- Leederville Precinct Structure Plan boundary

Figure 1: Precinct boundary of the PDPF area


## 2.1.2 DEMOGRAPHICS

Data collected on the population, living and transport habits provides valuable insight into the community that inhabits the Pickle District in the City of Vincent.

The statistics on this page reflect a growing inner-city community. The population is generally young, but has a low number of children. The community is multicultural with higher rates of residents speaking languages other than English at home, and having been born overseas.

Dwellings in West Perth are generally higher density and smaller in size, with most (35.4%) having two bedrooms, compared to Greater Perth in which most (37.9%) have four bedrooms. The number of households with children remains low, but has increased since 2016.

West Perth residents have more environmentally sustainable transport behaviours than residents of Greater Perth. A high number of residents do not own a car, and travel using public transport or active modes of transport.




### Community



West Perth's population in the City of Vincent is **2,321**. This is a 5.9% increase since 2016.

The median age is **33** compared to **37 in Greater Perth**.



**39.6% of residents** were born overseas compared to **36% in Greater Perth** (UK 7.5%, India 2.3%, NZ 2.3%).

**25.4% of residents** use a language other than English at home, compared to **20.9% in Greater Perth** (Mandarin 2.8%, Italian 2.5%, Spanish 2.2%).



In City of Vincent from 2016 to 2021:

- 44.6%** of people did not change address;
- 41.2%** moved from elsewhere in Australia; and
- 8.5%** moved from overseas.

Of those who moved within Australia, **20.9%** moved within City of Vincent.

### Dwellings



The **Pickle District portion of West Perth** is mostly non-residential, with currently one singular household residing in the area.

There are **1,381** dwellings in the City of Vincent portion of West Perth. This is a 4.4% increase since 2016.

Occupancy is **87%** compared to **91.7% in Greater Perth**.

Average household size is **1.79 persons per dwelling** compared to **2.50 in Greater Perth**.



**54.1%** of dwellings are medium or high density compared to **24% in Greater Perth**.

**42.1%** of West Perth households in the City of Vincent are lone person households compared to **24% in Greater Perth**.

**15.1%** of households have children compared to **42.3% in Greater Perth**. This is a 3.6% increase since 2016.

### Transport



**13.3% of residents** do not own a car compared to **4.8% in Greater Perth**.



**18.1% of residents** travel to work on train or bus compared to **8.4% in Greater Perth**.



**10.7% of residents** commute using active modes of transport compared to **2.2% in Greater Perth**.

## 2.2 KEY STAKEHOLDERS

The future of the Pickle District is influenced by several different stakeholders including external agencies, the City and the community.

### 2.2.1 WHAT IS THE ROLE OF EXTERNAL AGENCIES?

DEPARTMENT	RESPONSIBILITIES	RELEVANT STRATEGIES & PLANS
Federal Government	Grants and infrastructure funding	N/A
Department of Planning Lands and Heritage (DPLH)	State level land use planning and management, and oversight of Aboriginal cultural heritage matters	<p>Perth and Peel @ 3.5 million sets out an overarching framework for the Perth and Peel region to shift to a more sustainable development pattern to accommodate a population of 3.5 million people by 2050. The City of Vincent is located within the Central Sub-Region of the framework. The framework indicates that there will be an additional 11,490 dwellings and 25,270 people in the City of Vincent by the year 2050.</p> <p>Metropolitan Region Scheme (MRS) broadly guides the distribution of land use throughout the Perth metropolitan region by designating 'zones' and 'reserves'. The northern side of Newcastle Street is zoned 'Urban' and the southern side of Newcastle Street is zoned 'Industrial'. An amendment to the MRS to rezone the land from 'Industrial' to 'Urban' is required.</p> <p>State Planning Policy 4.2: Activity Centres for Perth &amp; Peel (SPP 4.2) specifies requirements for the planning, design and development of new activity centres, and the redevelopment and renewal of existing centres in Perth and Peel. The section of West Perth that is south of Newcastle Street, the Pickle District, forms part of the Capital City. The main role of the Capital City is to provide the most intensely concentrated development in the region. It has the greatest range of high order services and jobs, and the largest commercial component of any activity centre.</p> <p>State Planning Policy 5.4: Road and Rail Noise (SPP 5.4) seeks to minimise the adverse impact of road and rail noise on sensitive land uses or developments within a specified distance of significant freight and traffic routes. The PDPF area is significantly affected by 'Other significant freight or major traffic route', 'Strategic freight or major traffic route' and the 'Metropolitan passenger railway'.</p> <p>State Planning Policy 7.3: Residential Design Codes (R-Codes) control the design of most residential development throughout Western Australia. The R-Codes aim to address emerging design trends, promote sustainability, improve clarity and highlight assessment pathways to facilitate better outcomes for residents.</p> <p>State Register of Heritage Places is a statutory list of places that represent the story of Western Australia's history and development. Places included in the State Register include buildings, structures, gardens, cemeteries, memorials, landscapes and archaeological sites. There are no state registered heritage places within the PDPF area.</p>
Main Roads WA (MRWA)	Management of Primary Distributor roads across the state of Western Australia. This includes Charles Street, the Mitchell Freeway and Graham Farmer Freeway	<ul style="list-style-type: none"> <li>• Central Area Transport Plan</li> <li>• Perth and Peel @ 3.5 Million</li> <li>• Transport @ 3.5 Million</li> <li>• Policy for Cycling Infrastructure (2000)</li> </ul> <p>For further context, refer to Vincent's Accessible City Strategy.</p>

Department of Transport (DoT)	Working collaboratively with local government to develop strategic cycling networks for the region and providing grant funding for implementation of Western Australian Bicycle Network (WABN) routes	<ul style="list-style-type: none"> <li>• Central Area Transport Plan</li> <li>• Perth Parking Management Area (PPMA)</li> <li>• Public Transport for Perth in 2031</li> <li>• Perth and Peel @ 3.5 Million</li> <li>• Transport @ 3.5 Million</li> <li>• WA Bicycle Network</li> </ul>
Public Transport Authority (PTA)	<p>The PTA is responsible for:</p> <ul style="list-style-type: none"> <li>• Train services</li> <li>• Number and frequency of bus routes throughout the City</li> <li>• Ensuring that bus stops comply with the Disability Standards for Accessible Public Transport, including constructing level concrete hard-stand boarding areas and up to 3m of pathway connecting to existing footpath networks</li> <li>• Supporting the implementation of transit-supportive infrastructure by LGAs, including roadside bus shelters</li> <li>• Work collaboratively with MRWA and local government to introduce bus priority lanes</li> </ul>	<ul style="list-style-type: none"> <li>• Central Area Transport Plan</li> <li>• Draft Public Transport for Perth in 2031</li> <li>• Perth and Peel @ 3.5 Million</li> <li>• Transport @ 3.5 Million</li> <li>• Accessibility Policy (2007)</li> </ul>
DevelopmentWA - Formally known as the Metropolitan Redevelopment Authority (MRA) and LandCorp.	<p>DevelopmentWA which is the State Government's central development agency, operates across Western Australia with a diverse portfolio of industrial, commercial and residential projects.</p> <p>DevelopmentWA is responsible for the redevelopment of the East Perth Power Station. The eventual redevelopment of this site will further aid in the revitalisation of the wider North Claisebrook/East Perth area.</p>	<ul style="list-style-type: none"> <li>• East Perth Power Station Redevelopment</li> <li>• Subiaco Oval and Princess Margaret Hospital Redevelopment (Subi East)</li> <li>• Elizabeth Quay</li> <li>• Yagan Square</li> </ul> <p>For further context, portions of the NCPF area were once under the management of the East Perth Redevelopment Authority (a precursor to the MRA).</p>
Water Corporation WA	Management of water supply in Western Australia.	<ul style="list-style-type: none"> <li>• State Planning Policy No.3 – Urban Growth and Settlement</li> <li>• Review of Local Planning Schemes and Strategies as they are amended</li> </ul>
Neighbouring Local Government Authorities	Working collaboratively to ensure strong connections between localities	<ul style="list-style-type: none"> <li>• Various Planning Schemes</li> <li>• Transport and Urban Design plans and policies</li> <li>• Parking approaches</li> </ul>

## 2.2.2 WHAT IS THE ROLE OF THE CITY?

The City are the key point of contact for our community. The City are responsible for balancing the needs of residents, schools, community groups and local businesses with legislative requirements and an established strategic direction.

The City has authority over a series of localised infrastructure within the public realm including, but not limited to, local streets, footpaths, shared paths and cycle infrastructure, and street furniture including street lighting.

The City also have the ability to influence development outcomes within the private realm through land use planning, zoning regulations, and built form requirements. This can have a significant impact on the physical and economic outcomes of an area.

Advocating to State Government bodies will continue to be important role for the City as we continually strive to influence outcomes that are beyond our control.







Vincent plays a critical role in attracting and retaining businesses and industries within areas. By offering incentives that benefit the community, there is opportunity to create well designed and thriving places that meet the needs of its current and future residents, business owners and visitors.

## STRATEGIC CONTEXT

All local governments are required to have a plan for the future. This takes the form of a Strategic Community Plan (SCP), an overarching document informed by extensive community consultation. It sets the strategic direction for the entire organisation and is supported by a number of informing strategies and plans. One of these is the PDPF. The vision for the City of Vincent has been agreed as:

*"In 2028, The City of Vincent is a leafy vibrant 24-hour city, which is synonymous with quality design and sustainability. Its diverse population is supported in their innovative endeavours by a council that says YES!"*

The relationship between the Guiding Principles of the SCP and the PDPF are highlighted below:

GUIDING PRINCIPLE	SCP INTENT	APPLICATION TO THE PDPF
 <b>ENHANCED ENVIRONMENT</b>	The natural environment contributes greatly to our inner-city community. We want to protect and enhance it, making best use of our natural resources for the benefit of current and future generations.	<ul style="list-style-type: none"> <li>Provide guidance to maximise on-site landscaping.</li> <li>Identify opportunities for public open space, or cash-in-lieu of public open space.</li> <li>Seek opportunities in the public realm for planting.</li> </ul>
 <b>ACCESSIBLE CITY</b>	We want to be a leader in making it safe, easy, environmentally friendly and enjoyable to get around Vincent.	<ul style="list-style-type: none"> <li>Enforce maximum parking ratios in line with the Perth Parking Policy.</li> <li>Analyse and improving cycle routes.</li> <li>Improve pedestrian experience through built form and canopy coverage.</li> </ul>
 <b>CONNECTED &amp; HEALTHY COMMUNITY</b>	We are a diverse, welcoming and engaged community. We want to celebrate what makes us unique and connect with those around us to enhance our quality of life.	<ul style="list-style-type: none"> <li>We engaged with the local community, businesses and the Town Team throughout the development of this framework.</li> <li>Encourage community spaces within new development.</li> <li>Encourage inclusive and accessible development beyond the minimum requirements of the Building Codes Australia.</li> </ul>
 <b>THRIVING PLACES</b>	Thriving Places are integral to our identity, economy and appeal. We want to create, enhance and promote great places and spaces for everyone to enjoy.	<ul style="list-style-type: none"> <li>Encourage local and small businesses.</li> <li>Require development outcomes that enhance the public and private realms.</li> <li>Identify opportunities to improve the pedestrian experience within the private and public realms.</li> <li>Encourage public art and activation.</li> </ul>
 <b>SENSITIVE DESIGN</b>	Design that 'fits in' to our neighbourhoods is important to us. We want to see unique, high quality developments that respect our character and identity and respond to specific local circumstances.	<ul style="list-style-type: none"> <li>Built form provisions encourage attractive and diverse development in line with the community vision.</li> <li>Built form character and heritage is protected and enhanced.</li> <li>Support quality design, sustainable urban built form and is responsive to the community and local context.</li> <li>Encourage more people living in, working in, or enjoying the area.</li> </ul>
 <b>INNOVATIVE &amp; ACCOUNTABLE</b>	We have a significant role to play in supporting our community to realise its vision. To achieve this, we will be an innovative, honest, engaged and responsible organisation that manages resources well, communicates effectively and takes our stewardship role seriously.	<ul style="list-style-type: none"> <li>Engage with the community so they are involved in the development of this framework.</li> <li>Enable consistent and transparent decision making in line with its strategic vision.</li> </ul>

## INTEGRATED PLANNING AND REPORTING FRAMEWORK:

Local Governments are required to plan for the future in accordance with section 5.56 (1) of the *Local Government Act 1995* (Act). The Integrated Planning and Reporting Framework (IPRF) provides an integrated approach to planning and ensures community priorities and aspirations are translated into operational objectives by the City.

The IPRF incorporates the City's current SCP and Corporate Business Plan (CBP) and creates a clear vision for the future, including financial implications of the City.


The CBP is an internal business planning document that translates the Council's priorities, as set out in the SCP, into outcomes within the resources available to the City. The CBP is a rolling four-year plan that informs the annual budget and is reviewed and updated annually in order to ensure it aligns with the City's Long-Term Financial Plan (LTFP).

The PDPF includes guidance for future improvements to the Private and Public Realm.

Part 4 - Private Realm exists in the built form and land use. This section articulates the preferred design outcomes for the precinct area by providing design guidance. The principles are to guide contemporary built form and deliver a wide range of outcomes through new development and urban renewal.

Part 5 - Public Realm takes the form of a Place Plan. This section provides a filter for the place-based initiatives within the City's suite of informing strategies and plans, and directly informs the Corporate Business Plan.

The role of the Planning Framework within the City of Vincent IPRF is illustrated adjacent.



### 2.2.3 WHAT IS THE ROLE OF THE COMMUNITY?

The community helps to establish the strategic direction of the City of Vincent through the SCP. The SCP outlines the vision for the City and provides guidance for how planning, budgeting, resource allocation and service delivery should occur.

The SCP is divided into six Priority Areas and related outcomes and actions. Plans and strategies developed by the City must show alignment with the SCP pillars and are typically advertised for public comment and brought before the City's Council of Elected Members, who have an important policy-making function and advocate for community members.


Our community has determined that the Pickle District should retain its built form character and continue to grow its identity as an arts hub as it enters into a phase of redevelopment. Density should be increased with the provision of varied and inclusive residential offerings, high quality design and architecture, public outdoor spaces and increased planting.

The wider West Perth community are an engaged group that care about built form, particularly regarding heritage and character, connectivity and traffic.

The vast majority of the PDPF area community are businesses. In recent years a number of arts and cultural businesses such as galleries, art studios, co-working and event spaces have moved into the area and the precinct has emerged as an inner city arts precinct. This has been further boosted by The Pickle District Town Team, formed by a number of local creative businesses in 2018. The town team aim to engage with the community to make the precinct a vibrant pocket of Perth, and have become well known for their annual after dark art crawl where local creatives collaborate to put on the event.

As a community, there is the opportunity to be involved in defining the vision for the Pickle District and the projects located within the precinct through community and stakeholder engagement conducted by the City. The opportunity also exists to make behavioural changes to support the vision and goals of this framework, such as opting for active or public modes of transport where possible and supporting the local businesses, particularly the creative industries.

Further outlined in section 05 The Public Realm - Place Plan, the community also has the opportunity to engage in particular initiatives such as the design of public open space, community activations and public art procurement.



## 2.3 WHERE ARE WE NOW?

A series of investigations to identify the strengths, weaknesses, opportunities and threats (SWOT) associated with the existing development, land use, connectivity, culture, and public realm outcomes of the area.

This includes:

- Comprehensive desktop analysis, considering the history of area, and what is happening now.
- Review of statutory frameworks, strategies, policies and plans that impact the area.
- Site visits with all relevant areas of administration and external stakeholders.
- Site and context mapping analysis.

The SCP priority areas guided the context review. The following analysis provides an overview of the current context of the PDPF area and has allowed a SWOT analysis to be developed and therefore includes key recommendations for the PDPF.





## 2.3.1 ENHANCED ENVIRONMENT

Vincent's Greening Plan seeks to achieve 20 percent canopy coverage throughout Vincent by 2050. This can only be achieved through year on year increases to canopy coverage within the public and private realms. However, the PDPF area provides little contribution to Vincent's urban canopy.

Sutherland Reserve and the area adjacent to Old Aberdeen Place are well planted and contain significant trees. However, both parcels of land are not recognised as public open space due to their zoning under the MRS and LPS2.

Newcastle Street is lined with trees however the aboveground power lines impact the extent of canopy that is provided by those trees.

Redevelopment of sites will create opportunity for greater deep soil area and canopy coverage within the public and private realms.

Ceding land for public open space or paying cash-in-lieu of public open space will improve the amenity of, and increase the amount of public open space within the locality.

Opportunities for on-structure planting should be considered to further increase the amount of landscaping within the precinct area.

### LEGEND







-  TREES OF SIGNIFICANCE
-  FORMAL AND INFORMAL TREES
-  PUBLIC OPEN SPACE
-  UNSHADED FOOTPATHS
-  400 METRE RADIUS
-  TOWN CENTRE / PRECINCT BOUNDARY



Figure 2: Canopy coverage and public open space within the PDPF area

## 2.3.2 ACCESSIBLE CITY

The PDPF area is in close proximity to Perth CBD and Leederville Town Centre. It is provided with free public transit along Newcastle Street up until Loftus Street. It also sits within the Perth Parking Management Area (PPMA) with the PPMA Policy restricting the number of car bays that can be provided within the PDPF area.

Access to the Graham Farmer Freeway is provided via Loftus Street and the Mitchell Freeway. The on-ramp from these roads is directly south of the PDPF area. Vehicles heading east along the Loftus Street connection can exit into the area. Changes to this intersection are recommended to improve pedestrian safety.

The area provides cycle access via:

- Primary cycle route 3,279: runs adjacent to the freeway, connects destinations of regional importance, and is for medium and long distance commuting.
- Secondary route 4,509: runs along Loftus Street. It provides connectivity between primary routes and major activity centres including those within Vincent.
- Local route 3,231: runs along Golding Street. It provides critical access to higher order routes, local amenities and recreational spaces. It is a 'Safe Active Street' and prioritises cyclists.

The area is accessible via an off road path/Principal Shared Path (PSP). There is further opportunity to improve access to and from the area by:

- Creating a connection between Drummond Place and Loftus Street for people walking and riding;
- Introducing an east-west riding route along Drummond Place and Old Aberdeen Place that connects with the existing PSP;
- Improving activation of the area with improved wayfinding; and
- Enhancing the streetscape with street trees, furniture, footpaths and landscaping to facilitate further activation of the area.

All improvements that support active and public transport improve the areas and mitigate the need for excess parking within it.




Figure 3: Accessibility within and throughout the PDPF area


### 2.3.3 CONNECTED AND HEALTHY COMMUNITY

There is a strong sense of community within the PDPF area, which includes the Pickle District Town Team, and passionate residents who live north of Newcastle Street. Both groups have on numerous occasions advocated for protecting the arts and culture that lives within it.

More places for arts and culture are encouraged, along with new public or privately owned buildings that support community initiatives and events.

The community recognises that a mix of residential and non-residential development is required to support the economic growth in the area, and development incentives could be used to create the desired community benefit.

Map Title



## 2.3.4 THRIVING PLACES

The area south of Newcastle Street is zoned Commercial under LPS2. This has led to a large number of industrial and commercial land uses and day-time vibrancy within this area.

Many of the current land uses fall within the creative arts industry and support the community events that are run by the Pickle District Town Team.

There are some safety concerns within the area. This can be alleviated through the introduction of a greater mix of land uses that support the arts culture, night-time economy, and activated frontages.

Development incentives can support improvements to the area through initiatives such as lighting, seating, and support of the creative arts industry.

Newcastle Street North is predominately zoned Mixed-use R160 under LPS2. There has been little redevelopment over the years and the streetscape represents its historic built form with large street setbacks and limited street activation.

New development should be located closer to the street and provide activation through built form outcomes and appropriate land uses.

### LEGEND

- OPEN SPACE
- SPORT FACILITIES
- COMMUNITY SERVICES
- EDUCATION
- ARTS, CULTURE, ENTERTAINMENT
- COMMERCIAL
- INDUSTRIAL
- HOSPITALITY
- ACTIVE FRONTAGES
- PASSIVE FRONTAGES
- POOR FRONTAGES
- PUBLIC OPEN SPACE
- 400 METRE RADIUS
- PRECINCT BOUNDARY



Figure 4: Activation and places of interest within and adjacent to the PDPF area

## 2.3.5 SENSITIVE DESIGN

Currently, the PDPF area is significantly underdeveloped and predominantly comprises of single or two storey buildings.

The City's Local Planning Strategy has highlighted this area for urban growth and regeneration. There are many lots under single ownership creating opportunity for more efficient and creative use of the land.

The community and other key stakeholders have had significant influence over the vision of the area. Their sentiments are captured throughout the Framework.

To uphold the vision and deliver the desired outcomes of this Framework a MRS and LPS2 Amendment are required to support the future intent of the PDPF.

The City will continue to work closely with the DPLH and other relevant stakeholders to progress the MRS amendment to rezone the area south of Newcastle Street from 'Industrial' to 'Urban'.

Subsequently, the City will amend its LPS2 to rezone the area south of Newcastle Street from 'Commercial' to 'Mixed Use'.

### LEGEND

- 8 STOREYS
- 6 STOREYS
- 3 STOREYS
- 2 STOREYS
- 1 STOREY
- V VACANT
- PUBLIC OPEN SPACE
- SOLE OWNERSHIP LOT
- 400 METRE RADIUS
- PRECINCT BOUNDARY



Figure 5: Existing built form and development potential of th PDPF area

## 2.3.6 INNOVATIVE AND ACCOUNTABLE

The creation of a new planning framework that is bespoke to the area, guides development in line with the community's vision, and creates actions to address barriers demonstrates the City's desire and ability to be an innovative and accountable local government.

Map Title



## 2.4 STAKEHOLDER ENGAGEMENT

Stakeholder engagement was undertaken in the drafting of the PDPF. This has allowed the framework to be developed in line with both the context analysis undertaken and feedback received.

### 2.4.1 COMMUNITY ENGAGEMENT

The preparation of the PDPF included significant consultation with the wider West Perth community. Several consultation methods contributed to its development.

- A survey was posted on Imagine Vincent, running for the duration of the consultation period.
- A visioning workshop was held on Monday, 12 December 2022.
- A design workshop was held on Thursday, 16 February 2023.

Each engagement method sought to build upon the information obtained from the previous method. The key themes identified through consultation are as follows.

#### What the community wants to see:

- Creative arts land uses and public art
- Day and night time economy
- Fine grain public realm
- Industrial character mixed with contemporary development
- Outdoor spaces and trees

#### What the community doesn't want to see:



- Traffic and parking issues
- Franchises or major corporations
- Loss of character
- Loss of the arts precinct
- Poor pedestrian amenity

#### Where height should be located:

- Height was generally accepted but significant height should be located closer to the freeway
- Key development sites should be included in the framework

#### What the public and private realm should look like:

- There was overall agreement that there was no particular style that should be encouraged, but development should embrace good design principles
- Existing buildings should be retained or reused where possible (i.e. the Pickle Factory)
- There is a desire for creative land uses to be protected and prioritised within the area
- Improved landscaping and Environmentally Sustainable Design outcomes



## 2.4.2 TECHNICAL STAKEHOLDER ENGAGEMENT

The following comment was provided from various technical stakeholders:

### Design Review Panel

The Design Review Panel provided technical advice on 12 October 2022 and 22 March 2023.

Their advice considered outcomes of the community engagement activities, and highlighted areas of improvement within the public and private realms. The advice is incorporated throughout the Framework.

### Water Corporation

Based on the PDPF's proximity to the Perth CBD, the Leederville train station, the freeway and a broad range of local services and amenities, it appears to be well located and suitable for more intensive land development and a wider range of land uses.

Redevelopment of the area will place demands on the local networks that will be in excess of their design capacity. More detailed water and wastewater planning needs to be undertaken to determine the extent and location of required network upgrades.

### Main Roads WA

It is imperative that local governments and relevant state agencies look at the impact this zoning may have on the Mitchell Freeway and surrounding road networks. The Mitchell Freeway/Loftus Street Interchange is currently deemed as being built to ultimate design. However, with the probable increased demand on the transport network generated by the proposed zoning amendment, it will need to be determined by the DoT whether any further bridge crossings of the Freeway at this location are likely to occur (i.e. Light Rail or pedestrian crossing). Should any further crossing be deemed likely, then further land reservation will be required, probably in the north-east quadrant of the intersection of the Mitchell Freeway and Loftus Street.

### Servicing Reports

A dial before you dig request was generated. Key service providers within the precinct provided information regarding services and utilities within the area.

For further information, see Appendices.



---

## 2.4.3 DID WE GET IT RIGHT?

Guided by the City's Strategic Community Plan (SCP), with its foundation of engagement and the six Council Priorities of the SCP, the creation of this planning framework occurred in five milestones, in collaboration with the local community.

- Step 1 Understand the Pickle District from a technical perspective through research and site visits, culminating in a strengths, weaknesses, opportunities and threats analysis associated with the precinct's land use, connectivity, culture and public and private realm outcomes.
- Step 2 Inform the community and key stakeholders of our findings and seek input from the community as to what they value to establish a vision for the area and what the community values in the place. Understanding where the community is and where it wants to be formed the basis of the discussion around the first vision workshop held on 12 December 2022. The City engaged with landowners, business owners, local residents and visitors to the precinct directly to formulate the vision and objectives of this policy.
- Step 3 A draft vision for the precinct based on community feedback and to build on this draft vision by developing a design response for the precinct. A second design workshop held 16 February 2023 provided an opportunity for the community to refine the draft vision and help guide the development of the design response.
- Step 4 Collate responses from the vision and design elements of consultation, leading into the draft PDPF being advertised for 28 days, from 29 May to 26 June 2023.
- Step 5 Present the feedback received from each of these stages back to a meeting of council in August 2023 for final endorsement of the PDPF.

Through these milestones, the vision and design objectives have been tested and confirmed and are considered to reflect the community's future aspirations for the Pickle District in both the public and private realm.



# 03 WHERE DO WE WANT TO BE?

## 3.1 VISION

After establishing where we are now, it was determined what our major opportunities and threats would be in the future. Community consultation reinforced what we found and reaffirmed the findings of the SCP major review undertaken in 2021/22. The resulting vision for the Pickle District is as follows:

*South of Newcastle Street is the Pickle District and the heart of West Perth. It is a vibrant hub of art, culture, and entrepreneurship. The district's identity is grounded in its unique character and versatile land uses, catering to creative makers and innovative businesses alike. High-quality, inclusive residential developments are integrated with the creative industries that will flourish here. Every building will be a testament to great design and architecture, reflecting the high standards we set for ourselves and our community.*

*North of Newcastle Street connects the Pickle District to its surrounds. It provides a mix of land uses that are sympathetic to the adjoining low and medium density residential development. The public realm is a pleasant environment for pedestrians who utilise the free public transport or are actively transitioning to other places of interest.*

*A visual artist interpretation of the Community's Vision is demonstrated on the following page.*

## 3.2 DEVELOPMENT OBJECTIVES

The development objectives are drawn from conversation with the community and underpin the vision for the precinct. The objectives articulate the desired outcomes for development and support the urban renewal of the precinct.

Where development does not meet the acceptable outcomes, the development should be assessed against these objectives.

1. Enhance the creativity and uniqueness that lives within the precinct through the prioritisation of cultural infrastructure.
2. Invest in the community through opportunities that create inclusiveness, social interaction and connectedness.
3. Foster existing development, each with a distinctive character and sense of place.
4. Contribute to Vincent's green network by increasing green spaces and planting appropriate vegetation that will mitigate the urban heat island effect.
5. Deliver human-scale places with furniture, landscaping, activation, and public art.
6. Design places with fine grain and three dimensional detail that is visually interesting when viewed up close, where it matters most.
7. Implement sustainable and accessible transport initiatives, with greater emphasis and provision for walking, cycling, and public transport use.
8. Incentivise innovative and sustainable design that respects people, place and the planet.
9. Retain existing buildings (where appropriate) to maintain the industrial feel and be creative in the ways in which buildings are re-used and activated.

## 3.3 SUB-PRECINCT STATEMENTS OF INTENT

The PDPF area is made up of five sub-precincts shown in Figure 6, each with its own statement of intent. The Statements of Intent describe the importance of this area and what its contribution to the precinct should look like.

### 1. NEWCASTLE STREET NORTH

Newcastle Street serves as a vital link between the PDPF area, Leederville to the east, and Perth City via the long-term cycle network. To facilitate this connection, new development on the northern side of Newcastle Street should prioritise the enhancement of pedestrian amenity. This can be achieved through the provision of safe and convenient access and egress points, an abundance of shade trees, and the implementation of landscaped verges, upgraded footpaths, continuous awnings, and active frontages. Additionally, the existing roadway environment should be softened through the introduction of landscape treatments to create a more inviting and pleasant pedestrian experience.

It's important that any new developments are complementary to the adjacent residential properties to the north. As such, the land use mix and built form should be carefully considered to ensure a harmonious coexistence.


### 2. CITY MOTORS SITE

This is a key development site for this precinct. Its location allows for a significant height increase, with ample space to create a public open area that will add to the community's amenity.

A variety of land uses including boutique retail, food and beverage offerings, bars, businesses, space for art and culture, and music are incorporated into a high-quality environment, drawing people in from within and beyond West Perth. By providing high quality pedestrian amenity and connection to the remainder of the precinct, people will be able to explore the arts and creative culture that lives within it.

The existing development on the site comprises the Old Pickle Factory, unique roof forms, and a variety of colours, materials, and textures. New development should retain and celebrate these historic buildings and character elements that make the area different to any other in Vincent.

# ARTISTS INTERPRETATION OLD ABERDEEN PLACE



### 3. NO. 1 & 15 DRUMMOND PLACE

This is a key development site for the precinct. Its location allows for a significant height increase, with opportunity to enhance the pedestrian link between the precinct and Leederville.

New development will focus on the pedestrian experience by enhancing walkability, safety, and accessibility to the area. This may include measures such as creating wider sidewalks, active land uses, lighting, and benches. The development facing Simpson Street will be sympathetic to low density development and seek to mitigate adverse impacts with respect to access to natural sunlight and ventilation, privacy and built form.

### 4. SIMPSON STREET

Simpson Street comprises two residential style buildings and adjoins vacant state government owned lots, which currently function as public open space.

It is envisaged these sites will become part of the public open space that adjoins them.


### 5. NEWCASTLE STREET SOUTH

It is intended this precinct will provide visitors with an immersive experience that celebrates the vibrant and imaginative spirit of the area. The newly upgraded path on Drummond Place and access from Newcastle Street will act as gateways to this unique space, inviting people to explore and discover the dynamic range of land uses on offer.

This precinct will be a hub of creativity, with dedicated spaces for creators and makers to showcase their talents. The existing industrial services that thrive within the area will also be integrated into new development, creating a rich and diverse tapestry of activity.

To further enhance the visitor experience, interesting laneways will be woven throughout the sites, connecting adjacent streets and providing visually captivating spaces for pedestrians to wander through. These laneways will also be utilised for events and activations, further activating the area and creating a sense of community.

While development will embrace modern architectural elements, the mix of buildings will pay homage to the existing character of the area. Careful consideration will be given to ensure that these elements are integrated in a tasteful and respectful manner, creating a seamless blend of old and new.



#### LEGEND

- 1. NEWCASTLE STREET NORTH (6 STOREYS)
- 2. CITY MOTORS SITE (ACCEPTABLE 7, MAX 23 STOREYS)
- 3. NO. 1 & 15 DRUMMOND PLACE (ACCEPTABLE 7, MAX 23 STOREYS)
- 4. SIMPSON STREET (N/A)
- 5. NEWCASTLE STREET SOUTH (ACCEPTABLE 7, MAX 14 STOREYS)

Figure 6: Sub-precinct areas

# 04 THE PRIVATE REALM - BUILT FORM

This section articulates the preferred design outcomes for the PDPF area by providing design guidance for development within the private realm.

The principles are to guide contemporary built form and deliver a wide range of outcomes, including cultural infrastructure, through new development and urban renewal.

Applicants are encouraged to engage with the City's Officers and Design Review Panel as early as possible to obtain feedback on proposals. The role of the City and Design Review Panel is to provide guidance on whether the development is meeting these principles of good design, the Vision, Objectives, and the Statements of Intent (described above).



## TEN PRINCIPLES OF GOOD DESIGN

- Context and Character – Good design responds to and enhances the distinctive characteristics of a local area, contributing to a sense of place.
- Landscape Quality – Good design recognises that together landscape and buildings operate as an integrated and sustainable system, within a broader ecological context.
- Built Form and Scale – Good design ensures that the massing and height of development is appropriate to its setting and successfully negotiates between existing built form and the intended future character of the local area.
- Functionality and Build Quality – Good design meets the needs of users efficiently and effectively, balancing functional requirements to perform well and deliver optimum benefit over the full life-cycle.
- Sustainability – Good design optimises the sustainability of the built environment, delivering positive environmental, social and economic outcomes.
- Amenity – Good design provides successful places that offer a variety of uses and activities while optimising internal and external amenity for occupants, visitors and neighbours, providing environments that are comfortable, productive and healthy.
- Legibility – Good design results in buildings and places that are legible, with clear connections and easily identifiable elements to help people find their way around.
- Safety – Good design optimises safety and security, minimising the risk of personal harm and supporting safe behaviour and use.
- Community – Good design responds to local community needs as well as the wider social context, providing environments that support a diverse range of people and facilitate social interaction.
- Aesthetics – Good design is the product of a skilled, judicious design process that results in attractive and inviting buildings and places that engage the senses.

## 4.1 LAND USES

Development should focus on creative, cultural, educational and entertainment activities that complement existing activities, whilst enhancing streetscape activation and creating places for interaction. Small and independent businesses are strongly encouraged to operate within the area.

When considering development applications for land uses that require approval, the decision maker shall have regard to the vision and objectives of the PDPF, and the objectives and provisions of LPS2.

The following table contains example land uses and activities that are preferred and can be contemplated.

Preferred uses are land uses which are considered to contribute to the precinct's Vision and Sub-precinct Statements of Intent.

Contemplated uses are land uses which are considered suitable if it can be demonstrated the land use will not detract from the precinct intent and the locality's amenity. The contemplated land uses should be coupled with the preferred uses.

Uses and activities that are not listed below may be considered inconsistent with the precinct development intent. They should be assessed against the Vision and Statements of Intent within this framework, the City's LPS2 and the Planning and Development (Local Planning Schemes) Regulations 2015.

PRECINCT	PREFERRED USES	CONTEMPLATED USES
<b>All Precincts south of Newcastle Street</b>	<ul style="list-style-type: none"> <li>• Art studios and galleries</li> <li>• Civic and community use</li> <li>• Creators and makers</li> <li>• Design and architecture firms</li> <li>• Dining and entertainment</li> <li>• Fashion and textile workshops and showrooms</li> <li>• Film and television production facilities</li> <li>• Industry (light and cottage)</li> <li>• Markets</li> <li>• Microbrewery</li> <li>• Museums and cultural centres</li> <li>• Performance spaces, such as theaters and music venues</li> <li>• Recreation - Private</li> <li>• Retail (up to 100sqm)</li> <li>• Small bar</li> <li>• Small businesses and start-ups</li> </ul>	<ul style="list-style-type: none"> <li>• Child Care</li> <li>• Industry (general)</li> <li>• Medical centre</li> <li>• Motor vehicle repair</li> <li>• Office</li> <li>• Retail (greater than 100sqm)</li> <li>• Permanent residential</li> <li>• Transient Residential (hotel, short stay)</li> </ul>
<b>Newcastle Street North</b>	As per the Zoning Table of Local Planning Scheme No. 2.	





## 4.2 SUBDIVISION

Subdivision of land is generally not supported but may be appropriate in the following exceptional circumstances:

- a. To realign lot boundaries without increasing the number of lots.
- b. To protect and conserve places of cultural or natural heritage.
- c. To allow for the provision of utilities and infrastructure.
- d. To allow for improved safety or design of roads.
- e. To satisfy a condition of development approval.
- f. To enable land assembly to facilitate a coordinated development outcome or community benefit.

## 4.3 PRIMARY REGIONAL ROAD

In accordance with State Planning Policy 5.4 Road and Rail Noise (SPP5.4), all new lots within the area that are intended for noise sensitive land uses must incorporate a notification on the relevant certificate(s) of title pursuant to Section 70A of the Transfer of Land Act 1893. Notice of this notification is to be included on the diagram or plan of survey.

The notification is to state as follows:

*“The lot is situated in the vicinity of a transport corridor and in close proximity to commercial and non-residential activities. The use or enjoyment of the property may be affected by increased noise levels resulting from live and/or amplified music, traffic, car parking and other impacts associated with nearby commercial and non-residential activities within the transport corridor.”*

All development must comply with the City’s Policy No. 7.5.21 – Sound Attenuation, SPP5.4 and the location of the primary regional road reserve.

## 4.4 GENERAL PROVISIONS

Development within the precinct shall be in accordance with the tables and provisions as follows.

These requirements are applicable to the Pickle District. In addition to the general requirements, the provisions of the R-Codes Volume 2 apply to mixed use and residential development.

To the extent of any inconsistency, a requirement in this section replaces the relevant provision of the R-Codes.

## 4.4.1 URBAN DESIGN STUDY

*In accordance with Schedule 2, Part 8, Clause 63 (c) of the Planning and Development (Local Planning Schemes) Regulations 2015).*

An Urban Design Study is to be submitted with the application for development approval and must consider all of the following local housing objectives:

- a. Appropriate use of a variety of materials and finishes that complement elements of the existing local character whilst avoiding the use of faux (made as an imitation, fake or false) materials.
- b. Articulation that uses architectural elements in addition to setbacks to reduce its impact on adjoining properties and improves the amenity of adjoining properties and the streetscape.
- c. Fire boosters, mail boxes and external fixtures that are integrated in the early design stage and located to minimise the impact on the public realm.
- d. Development that achieves visual interaction with the vehicle and pedestrian approaches.
- e. Development which integrates and/or acknowledges the design elements and character of the streetscape identified in the Urban Design Study.
- f. Development which incorporates the design elements of the predominant streetscape character.
- g. Development on corner sites that is designed to express significance and frame the corner to define the built form and give a strong edge to the public realm.
- h. Development expressed with strong visual elements that integrate with all street frontages and right of ways.
- i. Create cohesion of all street frontages and contribute to a comfortable pedestrian environment by addressing each frontage with passive surveillance and safe sight lines.
- j. Development shall integrate with adjoining public spaces by including visual surveillance or clearly visible entrances and paths directly onto the public space.
- k. Emphasize vertical articulation to break up building mass and highlight street level uses and details.
- l. Development designed to be adaptive and cater for changing uses over time within the relevant zone.
- m. High quality durable materials and textures used at street level and upper levels which express the architectural style of the surrounding context.
- n. Design which is responsive to any existing and/or proposed verge trees and will promote greening within the planning framework area.

---

## 4.4.2 STREET SETBACKS

*In addition to Acceptable Outcomes of Section 2.3 of R-Codes Volume 2.*

- 4.4.2.1 Where minimum street setbacks are required, the setback area shall be used for landscaping, alfresco seating or other amenities that improve the public realm.

---

## 4.4.3 PUBLIC DOMAIN INTERFACE

*In addition to Acceptable Outcomes of Section 3.6 of R-Codes Volume 2.*

- 4.4.3.1 Exposed boundary walls visible to the street are to incorporate the following design features:
- Indentations;
  - Varying heights;
  - Varying materials, colours and textures; and/or
  - Public artwork.





#### 4.4.4 PEDESTRIAN ACCESS AND ENTRIES

*In addition to Acceptable Outcomes of Section 3.7 of R-Codes Volume 2.*

- 4.4.4.1 Pedestrian access which is identifiable from the street and visitor car parking areas and other public area.
- 4.4.4.2 Access for pedestrians which directly fronts the primary street.
- 4.4.4.3 Internal ground floor level to be at grade.
- 4.4.4.4 Design of balustrades to be integrated into the design of the development.
- 4.4.4.5 Ramps are not to exceed 50 percent of the active frontage.

---

#### 4.4.5 VEHICLE ACCESS

*In addition to Acceptable Outcomes of Section 3.8 of R-Codes Volume 2.*

- 4.4.5.1 Service areas and vehicular access shall be:
  - a. Taken from the rear laneway or secondary street in the first instances; or
  - b. Collocated where taken from the primary street to maximise the width of active frontages;
- 4.4.5.2 Access to onsite car parking spaces to be provided:
  - a. Where available, from a right of way available for lawful use to access the relevant lot and which is adequately paved and drained from the property boundary to a dedicated road; or
  - b. From a secondary street where no right of way exists; or
  - c. From the primary street frontage where no secondary street or right-of way exists.
- 4.4.5.3 Access to a right of way is required to be trafficable to the nearest dedicated road. The cost to upgrade a right of way to make it trafficable is to be borne by the applicant.
- 4.4.5.4 Where vehicular access is provided from a street, all vehicles are required to enter and exit the site in forward gear.
- 4.4.5.5 Roller shutters, doors and screens are to be visually permeable.
- 4.4.5.6 Onsite parking for a development shall be located beneath or at the rear of buildings.
- 4.4.5.7 In a mixed-use development, car bays should be clearly signposted differentiating between the residential car bays and the commercial car bays.
- 4.4.5.8 Where on-site parking provided for customer/client use is not directly visible from the adjacent street, adequate signage is to be provided to promote public knowledge of and direction to the car park. This signage is to comply with the requirements of the City's Policy relating to Signs and Advertising.
- 4.4.5.9 Existing trees must not be removed to provide for vehicle access.
- 4.4.5.10 Each lot is to provide a maximum of one crossover.
- 4.4.5.11 The maximum width of a single crossover is 3m. The maximum width of a double crossover is 5m.



## 4.4.6 FACADE DESIGN

*In addition to Acceptable Outcomes of Section 4.10 of R-Codes Volume 2.*

- 4.4.6.1 Development which fronts the public realm shall provide active frontages including glazing, openings and operable windows to ensure activity, interaction and surveillance of the street.
- 4.4.6.2 Ground floor spaces shall have a finished floor level to finished ceiling level height of a minimum of 3.5m.
- 4.4.6.3 Identify key design elements in the local area and streetscape through an Urban Design Study and integrate the design elements into building facades visible from the public realm. Developments shall:
- Integrate high-quality, durable and diverse materials and finishes into the façade, avoiding reflective or glaring materials, and cosmetic or superficial attachments to the building;
  - Design appropriately scaled buildings, considering rhythm, proportion, and height;
  - Incorporate vertical articulation by using tall and narrow facade treatments;
  - Provide ground floor facades that balance human scale design by providing obvious and entrances, fine grain development and active facades;
  - Not present a blank, monotonous, repetitious or dominant building treatment, unless it is in keeping with the streetscape character;
  - Incorporate architectural or functional elements integrated into the façade, rather than cosmetic or superficial attachments to the building;
  - Incorporate articulation such as doorways, windows, seating ledges, sills, stall raisers and other three-dimensional detailing;
  - Integrate fire boosters, mail boxes and external fixtures into the building design or screen them so they appear as part of the facade; and
  - Signage is to be minimal and integrated into the design of the building on the ground floor.
- 4.4.6.4 Ground floor glazing and/or tinting shall have a minimum of 70 percent visible light transmission to provide unobscured visibility.
- 4.4.6.5 Security measures shall be:
- Located and installed internally behind the glazing line or recessed between elements in the facade such as columns or doorway recesses; and
  - Transparent and visually permeable to allow views inside the building and enable internal light sources to be seen from the street.
- 4.4.6.6 Verandahs and colonnades are only permitted where they are constructed wholly within the lot boundaries of development site.
- 4.4.6.7 Development incorporates good passive solar design principles that reduce the reliance on mechanical systems for heating and cooling when designing the building facade.
- 4.4.6.8 The design, activation and materials of a building on a corner site should be articulated and expressed volumetrically, addressing both primary and secondary streets. In particular, the quality of the primary and secondary façade of the ground floor should be of similar quality.





## 4.4.7 PROJECTIONS AND AWNINGS

*In addition to Acceptable Outcomes of Section 4.10 of R-Codes Volume 2.*

- 4.4.7.1 Where weather protection along footpaths adjoining commercial and mixed use buildings is provided, they shall satisfy the following requirements:
- The weather protection will be integrated with the building design;
  - The weather protection shall be permanently fixed and shall be constructed of durable materials that provide sun and rain protection;
  - The weather protection shall project a minimum horizontal depth of 2.4m over the adjacent footpath; and
  - Awnings shall have a consistent clear height from footpath level between 2.75m and 3.5m;
- 4.4.7.2 Minor projections as defined by the R-Codes are excluded from the maximum building height calculation.
- 4.4.7.3 Balconies may project into the setback area, provided that such a projection complies with privacy requirements of the R-Codes.

---

## 4.4.8 MATERIALS AND FINISHES

*In addition to Acceptable Outcomes of Section 4.10 of R-Codes Volume 2.*

- 4.4.8.1 New development must be of a high architectural quality, incorporating articulated facades with large openings to the street or clear glazing, fenestration, parapet treatments and other detailing and materials that respect and complement the established character of the area.

---

## 4.4.9 ROOF DESIGN

*In addition to Acceptable Outcomes of Section 4.11 of R-Codes Volume 2.*

- 4.4.9.1 Flat roof structures shall have a maximum solar absorptance rating of 0.4.
- 4.4.9.2 Pitched roof structures or roof structures that are visible from the street or adjacent properties shall have a maximum solar absorptance rating of 0.5, unless a suitable alternative is identified in the Urban Design Study.

---

## 4.4.10 LIFT OVER-RUNS, ROOFTOP PLANT ROOMS AND ARCHITECTURAL FEATURES

*In addition to Acceptable Outcomes of Section 4.11 of R-Codes Volume 2.*

- 4.4.10.1 All lift over-runs and plant equipment must be adequately hidden from public view. This should be done through the design of the building rather than with a screening device that is visible to the public view.
- 4.4.10.2 Lift over-runs and rooftop plant rooms must not exceed 3.5m above the applicable maximum building height.

## 4.4.11 FUTURE REUSE

*In addition to Acceptable Outcomes of Section 4.13 of R-Codes Volume 2.*

4.4.11.1 New buildings must be designed with a minimum 3.5m floor to ceiling height on the ground floor and all levels of parking to allow future adaptation in use. This could include ground floor tenancies being adapted from office to restaurant or parking structures being converted to habitable spaces in the future.

4.4.11.2 All developments (residential and non-residential) shall have regard to the following:

- a. The structure of the building including the design of the elevation and location of openings designed to allow use for habitable purposes in the future; and
- b. Ground floor commercial tenancies shall be designed with space for infrastructure such as grease traps, exhaust ducts and power supply to allow future adaptation into other uses which require these services such as restaurants and cafes.

---

## 4.4.12 LANDSCAPING

*New residential and mixed-use development are strongly encouraged to satisfy clause 4.4.12. The following does not apply to alterations or additions to existing developments.*

4.4.12.1 A landscape plan, prepared by a suitably qualified consultant, must be provided with all multiple dwellings, commercial and mixed-use development applications. The landscaping plan must include a species list and irrigation plan and is to be in accordance with the Residential Design Codes.

4.4.12.2 Development applications for commercial development must satisfy the following:

- a. A minimum of 12 percent of the site area shall be provided Deep Soil Area (DSA). The Deep Soil Area shall have a minimum dimension of 1sqm (1m x 1m);
- b. A minimum of 3 percent of the site area shall be provided as Planting Area. The Planting Area shall have a minimum dimension of 1sqm (1m x 1m);
- c. Where the required deep soil area cannot be provided due to site constraints, planting areas are to be provided within structures at a rate of double the shortfall in deep soil area;
- d. Where a lot boundary setback applies, 80 percent of that area at ground level must be provided as canopy cover at maturity; and
- e. Existing trees on a property must be retained where they meet the following criteria:
  - i. Healthy specimens with ongoing viability;
  - ii. Species is not on the State or local weed register;
  - iii. Height of at least 4m, or trunk diameter of 160mm measured 1m from the ground, or average canopy diameter of at least 4m;
- f. The proposed removal of any tree that meets clause 4.4.9.2 (above) is to be provided with an arboriculture assessment;
- g. Where removal is deemed appropriate by the arboriculture assessment the trees must be replaced;
- h. The proposed removal of any native vegetation is to be supported by a flora and fauna assessment; and
- i. Uncovered car parking at ground level must be provided with canopy cover at maturity of at least 60 percent.

---

## 4.4.13 SERVICING AND FUNCTIONALITY

4.4.13.1 Waste storage facilities are to be provided on site and in accordance with City of Vincent waste guidelines for new developments;

4.4.13.2 Waste storage facilities are to be screened from direct public view.

4.4.13.3 Residential Waste storage areas must be separated from non-residential storage areas.

4.4.13.4 A Waste Management Plan is required for all residential properties over two dwellings, Mixed Use Developments, Commercial, Industrial and other non-residential developments.

---

## 4.4.14 HERITAGE AND CHARACTER MANAGEMENT

4.4.14.1 New buildings adjacent to character buildings, identified through the Urban Design Study, shall have an architectural character that respects and complements the existing surrounding character buildings. This character should draw from prominent materials and colours of the area and shall express and strengthen the intended place identity.

4.4.14.2 Contemporary architectural styles are acceptable provided they are designed manner that creatively interprets materials, forms, and patterns of the locality.



## 4.4.15 ENVIRONMENTALLY SUSTAINABLE DESIGN

New residential and mixed-use development are strongly encouraged to satisfy clause 4.4.15. The following does not apply to alterations or additions to existing developments.

4.4.15.1 Development that considers the whole of life environmental impact of the building and incorporates measures to reduce this impact;

4.4.15.2 Development shall incorporate:

- Site planning principles that maximise solar passive design opportunities for both summer and winter; and
- Recovery and re-use of rainwater, storm water, grey water and/or black water for non-potable water applications.

4.4.15.3 Development is encouraged to achieve the environmental performance standards shown in the below table, or their equivalent\*.

4.4.15.4 A variety of Water Sensitive Urban Design (WSUD) principles are encouraged to be incorporated into every development within the precinct. These include:

- On site storm water retention and detention for the 1 year, 1 hour ARI event;
- Water and nutrient wise landscaping;
- Permeable paving and ground covers;
- Rain gardens, bio filters, tree pits, green walls and vegetated soak wells; and
- Rainwater tanks, either for garden use or plumbed back into a building for reuse.

ACCEPTED RATING FRAMEWORK	SPECIFICATION/COMPLIANCE REQUIREMENTS	MINIMUM REQUIREMENTS TO BE ACHIEVED	EVIDENCE
Green Building Council of Australia's Green Star Rating System.	Current design and As-built rating tool.	5-star Green Star rating.	Preliminary Sustainable Design Report prepared by a Green Star Accredited professional using the current Green Star Design and As-built rating tool scorecard to demonstrate eligibility for 5-star Green Star rating.
Life Cycle Assessment in accordance with EN15978 - Sustainability of Construction Works – assessment of environmental performance of buildings – calculation method.	System boundary must include all Life Cycle Modules (A1-2, B1-7, C1-4 and D) in addition to non-integrated energy (plug loads).	Global Warming Potential and Net Fresh Water Use performance reduction as per Table *** below.	Independently reviewed EN15978 compliant target setting LCA with a 20 percent factor of safety applied to improvement strategies.
BUILDING TYPE		PERFORMANCE UNIT	
		GLOBAL WARMING POTENTIAL	NET FRESH WATER USE
<b>Suburban Frame</b>	<2,250 kgCO <sub>2</sub> e/occupant/year (50 percent saving against Perth statistical average residences).	<57m <sup>3</sup> /occupant /year (50 percent saving against Perth statistical average residences).	
<b>Commercial Office (BCA Class 5)</b>	<104 kgCO <sub>2</sub> e/m <sup>2</sup> net lettable area/year (30 percent saving against Perth statistical average office).	<1.25m <sup>3</sup> /m <sup>2</sup> net lettable area/year (25 percent saving against Perth statistical average office).	
<b>All Other Building Types</b>	30% saving against code-compliant design.	25% saving against code-compliant design.	

\*The City accepts sustainability assessment frameworks and mechanisms that are nationally or internationally recognised, compliant with applicable Australian/international standards and subject to oversight by a certifying body.

## 4.4.16 SAFETY, LIGHTING AND CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN

- 4.4.16.1 All areas of the private and public realms, especially places with lower volumes of foot traffic, must be adequately lit and designed to ensure that sightlines are provided from areas of high pedestrian traffic.
- 4.4.16.2 Lighting is provided to all areas that can be accessed by pedestrians.

---

## 4.4.17 PAYMENT IN LIEU OF PUBLIC OPEN SPACE RESERVES

- 4.4.17.1 Pursuant to s.153(1)(b) of the *Planning and Development Act 2005*, all subdivision of land that creates three or more lots must be subject to a condition requiring that the owner of the land to cede up to 10 percent of that land for the purpose of public open space, or make a payment equal to 10 percent of the value of that land to the local government.
- 4.4.17.2 Sub-clause '4.4.16.1' applies to all subdivision types including strata, survey strata, freehold, and community title. If a portion of land is subject to multiple eligible subdivisions, that portion of land will only be required to contribute once.

---

## 4.4.18 ROAD RESERVES, LANEWAYS AND PEDESTRIAN LINKS

- 4.4.18.1 Construction of a laneway or pedestrian link provided in accordance with Clause 6.1 is to be constructed by the owner/applicant.

As a condition of development or subdivision approval, properties affected by a road reservation are required to vest that portion of road reserve to the Crown as a condition of development or subdivision approval, whichever occurs first.

The City will provide technical advice on the detailed design.


Note: Implementation of Parklets within on street parking bays to support commercial uses and to slow vehicle movement is encouraged.

---

## 4.4.19 PARKING

- 4.4.19.1 Parking is to be accordance with the Perth Parking Policy 2014 (as amended), Local Planning Policy: Non-Residential Parking, and the R-Codes.

Note: The Perth Parking Policy 2014 prevails over the Local Planning Policy: Non-Residential Parking, and the R-Codes.



## 4.5 SPECIFIC DEVELOPMENT PROVISIONS

In accordance with clause 1.2.2 of R-Codes Volume 2, this Policy contains provisions that amend or replace the Acceptable Outcomes set out in Parts 2, 3 and 4 of the R-Codes Volume 2. The Element Objectives of the R-Codes Volume 2 remain and apply. The table below details which Acceptable Outcomes of the R-Codes Volume 2 have been amended or replaced by Acceptable Outcomes within the Local Planning Policy.

In assessing applications for development approval and local development plans the City shall have regard to the Policy Objectives of this Policy, the intent statement of each sub precinct and the general provisions included under Part 3 and Part 4 of this Policy.

TABLE OF MODIFICATIONS FOR STATE PLANNING POLICY 7.3 RESIDENTIAL DESIGN CODES VOLUME 2 (APARTMENTS)						
R-CODE VOLUME 2 DESIGN ELEMENT		APPLICABLE SUB-PRECINCT CLAUSE NUMBER				
PRECINCT	1. NEWCASTLE STREET NORTH	2. CITY MOTORS SITE	3. NO. 1 & 15 DRUMMOND PLACE	4. SIMPSON STREET	5. NEWCASTLE STREET SOUTH	APPLICABLE ACCEPTABLE OUTCOMES
<b>Part 2 - Primary Controls</b>						
<b>2.2 Building height</b>	A1.1 - A1.2	A2.1 - A2.3	A3.1 - A3.3	N/A	A5.1 - A5.3	Clause A1.1 - A1.2, A2.1 - A2.3, A3.1 - A3.3 and A5.1 - A5.3 of this Policy replaces Acceptable Outcome A 2.2.1 of the R-Codes Volume 2.
<b>2.3 Street setbacks</b>	A1.3 - A1.4	A2.4 - A2.6	A3.4 - A3.6	N/A	A5.4 - A5.6	Clause A1.3 - A1.4, A2.4 - A2.6, A3.4 - A3.6, A5.4 - A5.6 of this Policy replaces Acceptable Outcome A 2.3.1 of the R-Codes Volume 2.
<b>2.4 Side and rear setbacks</b>	A1.5 - A1.8	N/A	N/A	N/A	A5.7 - A5.9	Clause A1.5 - A1.8 and A5.7 - A5.9 applies in addition to Acceptable Outcome A2.4.1 and A2.4.2 of the R-Codes Volume 2.
<b>2.5 Plot ratio</b>	N/A	A2.7	A3.7	N/A	A5.10	Clause A2.7, A3.7 and A5.10 replaces Acceptable Outcome A2.5.1 of the R-Codes Volume 2. For sub-precinct 1 (Newcastle Street North), A2.5.1 of the R-Codes Volume 2 remains and applies.
<b>2.8 Development incentives</b>	N/A	Clause 4.6	Clause 4.6	N/A	Clause 4.6	Clause 4.6 applies to sub-precincts 2 (City Motors Site), 3 (No. 1 &15 Drummond Place), and 5 (All other areas). Clause 4.6 does not apply to sub-precincts 1 (Newcastle Street North) and 4 (Simpson Street).
<b>Part 3 - Siting the Development</b>						
<b>3.6 Public domain interface</b>	Clause 4.4.3	Clause 4.4.3	Clause 4.4.3	N/A	Clause 4.4.3	Acceptable Outcomes A3.6.1 - A3.6.9 remain and apply to all areas except sub-precinct 4 (Simpson Street).
<b>3.7 Pedestrian access and entries</b>	Clause 4.4.4	Clause 4.4.4	Clause 4.4.4	N/A	Clause 4.4.4	Clause 4.4.3 applies in addition to Acceptable Outcomes A3.7.1 - A3.7.6 of the R-Codes Volume 2.
<b>3.8 Vehicle Access</b>	Clause 4.4.5	Clause 4.4.5	Clause 4.4.5	N/A	Clause 4.4.5	Clause 4.4.4 applies in addition to Acceptable Outcomes A3.8.1 - A3.8.7 of the R-Codes Volume 2.
<b>Part 4 – Designing the Building</b>						
<b>4.10 Façade design</b>	Clause 4.4.6 - 4.4.8 and A1.9 - A1.12	Clause 4.4.6 - 4.4.8	Clause 4.4.6 - 4.4.8	N/A	Clause 4.4.6 - 4.4.8	Clause 4.4.5 - 4.4.7 and A1.9 - A1.12 applies in addition to Acceptable Outcomes A4.10.1 - A4.10.6 of the R-Codes Volume 2
<b>4.11 Roof design</b>	Clause 4.4.9 - 4.4.10 and A1.13	Clause 4.4.9 - 4.4.10	Clause 4.4.9 - 4.4.10	N/A	Clause 4.4.9 - 4.4.10	Clause 4.4.9 - 4.4.9 applies in addition to Acceptable Outcomes A4.10.1 - A4.10.6 of the R-Codes Volume 2. A1.13 also applies in addition to Acceptable Outcomes A4.10.1 - A4.10.6 of the R-Codes Volume 2 in sub-precinct 1 (Newcastle Street North)



#### 4.5.1 NEWCASTLE STREET NORTH

BUILDING HEIGHT		
R-Codes	Replace	Remain
	Clause A 1.1 and A 1.2 of this Policy replaces Acceptable Outcome A 2.2.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 1.1	Acceptable height for development is 6 storeys in height.	
A 1.2	External fixtures may extend beyond the maximum height in Figure 6 where they are not visible from the street or neighbouring properties.	

STREET SETBACKS		
R-Codes	Replace	Remain
	Clause A 1.3 and A 1.4 of this Policy replaces Acceptable Outcome A 2.3.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 1.3	First, second and third storey: nil setback.	
A 1.4	Fourth storey and above: 3m setback.	

SIDE AND REAR SETBACKS		
R-Codes	Replace	Remain
	Clause A 1.5 to A 1.8 of this Policy applies in addition to Acceptable Outcome A2.4.1 and A2.4.2 of the R-Codes Volume 2.	Clause A 2.4.1 and 2.4.2 of the R-Codes Volume 2 remains and applies.
Acceptable Outcomes		
Boundary walls		
A 1.5	Boundary walls are permitted to side lot boundaries only.	
A 1.6	Boundary walls shall be located towards the front of the development site.	
Development adjoining rights of way		
A 1.7	Where development adjoins a right of way the setback shall be measured from the midpoint of the right of way.	
A 1.8	Development must address adjoining rights of way by providing passive surveillance and openings to the right of way.	

PLOT RATIO		
R-Codes	Replace	Remain
-		Clause A 2.5.1 of the R-Codes Volume 2 remains and applies.

FACADE DESIGN		
R-Codes	Replace	Remain
	Clause A 1.10 to A 1.2 of this Policy apply in addition to Acceptable Outcome A 4.10.1 to A 4.10.6 of the R-Codes Volume 2.	Acceptable Outcome A 4.10.1 to A 4.10.6 of the R-Codes Volume 2 remains and applies.
Acceptable Outcomes		
A 1.9	Where provided, doorways shall have a depth between 500mm and 1.5m to clearly articulate entrances to commercial buildings and tenancies.	
A 1.10	Where provided, windows, seating ledges, sills, stall risers and other detailing shall have a minimum depth of 300mm.	
A 1.11	Where provided, stall risers shall be a minimum height of 450mm.	

PROJECTIONS AND AWNINGS		
R-Codes	Replace	Remain
	Clause A 1.12 of this Policy applies in addition to Acceptable Outcome A 4.10.1 to A 4.10.6 of the R-Codes Volume 2.	Acceptable Outcome A 4.10.1 to A 4.10.6 of the R-Codes Volume 2 remains and applies.
Acceptable Outcomes		
A 1.12	Provide protective continuous awnings over the pedestrian footpath are provided, which shall: <ul style="list-style-type: none"> <li>• Awnings shall have a consistent clear height from footpath level between 2.75m and 3.5m.</li> <li>• Be setback a minimum of 600mm from the face of kerb;</li> <li>• Respond to any existing and/or proposed verge trees;</li> <li>• Respond to the height, depth and form of existing awnings on the subject and adjoining buildings;</li> <li>• Respond to the slope of the site; and</li> <li>• Integrated with the design of the facade.</li> </ul>	

ROOF DESIGN		
R-Codes	Replace	Remain
	Clause A 1.13 of this Policy applies in addition to Acceptable Outcome A 4.11.1 to A 4.11.3 of the R-Codes Volume 2.	Acceptable Outcome A 4.11.1 to A 4.11.3 of the R-Codes Volume 2 remains and applies.
Acceptable Outcomes		
A 1.13	Any proposed usable roof space shall be situated adjacent to Newcastle Street and away from the neighboring residential properties situated to the north of the subject site.	







## 4.5.2 CITY MOTORS SITE

BUILDING HEIGHTS		
R-Codes	Replace	Remain
	Clause A 2.1 to A 2.3 of this Policy replaces Acceptable Outcome A 2.2.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 2.1	Maximum height for podium development is 4 storeys	
A 2.2	Acceptable height for tower development is 7 storeys	
A 2.3	Maximum height of tower development is 23 storeys subject to compliance with Clause 4.6 - Development incentives for community benefit.	

STREET SETBACKS		
R-Codes	Replace	Remain
	Clause A 2.4 to A 2.6 of this Policy replaces Acceptable Outcome A 2.3.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 2.4	Podium (up to four storeys): nil	
A 2.5	Tower (up to 8 storeys) <ul style="list-style-type: none"> <li>Graham Farmer Freeway: Minimum 4m</li> <li>Mitchell Freeway/Charles Street: Minimum 4m</li> <li>Golding Street: Minimum 6m</li> <li>Newcastle Street: 6m</li> </ul>	
A 2.6	Tower (9 storeys and above) <ul style="list-style-type: none"> <li>Graham Farmer Freeway: Minimum 6m</li> <li>Mitchell Freeway/Charles Street: Minimum 6m</li> <li>Golding Street: Minimum 12m</li> <li>Newcastle Street: 12m</li> </ul>	

SIDE AND REAR SETBACKS		
R-Codes	Replace	Remain
		Clause A 2.4.1 and 2.4.2 of the R-Codes Volume 2 remains and applies.

PLOT RATIO		
R-Codes	Replace	Remain
	Clause A 2.7 replaces Clause A 2.5.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 2.7	No requirement.	

### 4.5.3 NO. 1 & 15 DRUMMOND PLACE

#### HEIGHTS

R-Codes	Replace	Remain
	Clause A 3.1 to A 3.3 of this Policy replaces Acceptable Outcome A 2.2.1 of the R-Codes Volume 2.	
<b>Acceptable Outcomes</b>		
A 3.1	Maximum height for podium development is 4 storeys	
A 3.2	Acceptable height for tower development is 7 storeys	
A 3.3	Maximum height of tower development is 23 storeys subject to compliance with Clause 4.6 - Development incentives for community benefit.	

#### STREET SETBACKS


R-Codes	Replace	Remain
	Clause A 3.4 to A 3.6 of this Policy replaces Acceptable Outcome A 2.3.1 of the R-Codes Volume 2.	
<b>Acceptable Outcomes</b>		
A 3.4	Podium (up to four storeys) <ul style="list-style-type: none"> <li>• Drummond Place: nil</li> <li>• Simpson Street: 3m</li> <li>• Leederville Parade / Graham Farmer Freeway: Nil</li> </ul>	
A 3.5	Tower (up to 8 storeys) <ul style="list-style-type: none"> <li>• Drummond Place: 5m</li> <li>• Simpson Street: 5m</li> <li>• Leederville Parade / Graham Farmer Freeway: 4m</li> </ul>	
A 3.6	Tower (above 9 storeys) <ul style="list-style-type: none"> <li>• Drummond Place: 7m</li> <li>• Simpson Street: 7m</li> <li>• Leederville Parade / Graham Farmer Freeway: 6m</li> </ul>	

#### SIDE AND REAR SETBACK

R-Codes	Replace	Remain
	-	Clause A 2.4.1 and 2.4.2 of the R-Codes Volume 2 remains and applies.

#### PLOT RATIO

R-Codes	Replace	Remain
	Clause A 3.7 replaces Clause A 2.5.1 of the R-Codes Volume 2.	-
<b>Acceptable Outcomes</b>		
A 3.7	No requirement.	



---

## 4.5.4 SIMPSON STREET

Clause 23 and 24 of the Local Planning Scheme No. 2 applies.



## 4.5.5 NEWCASTLE STREET SOUTH

HEIGHTS		
R-Codes	Replace	Remain
	Clause A 5.1 to A 5.3 of this Policy replaces Acceptable Outcome A 2.2.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 5.1	Maximum height for podium development is 3 storeys	
A 5.2	Acceptable height for tower development is 7 storeys	
A 5.3	Maximum height of tower development is 14 storeys (49m) subject to compliance with Clause 4.6 - Development incentives for community benefit.	

STREET SETBACKS		
R-Codes	Replace	Remain
	Clause A 5.4 to A 5.9 of this Policy replaces Acceptable Outcome A 2.3.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 5.4	Podium (up to 3 storeys) <ul style="list-style-type: none"> <li>Primary setback: nil</li> </ul>	
A 5.5	Tower (up to 8 storeys) <ul style="list-style-type: none"> <li>Primary setback: 5m</li> </ul>	
A 5.6	Tower (9 storeys and above) <ul style="list-style-type: none"> <li>Primary setback: 7m</li> </ul>	

SIDE AND REAR SETBACKS		
R-Codes	Replace	Remain
	Clause A 5.7 to A 5.9 of this Policy applies in addition to Acceptable Outcome A2.4.1 and A2.4.2 of the R-Codes Volume 2.	Clause A 2.4.1 and 2.4.2 of the R-Codes Volume 2 remains and applies.
Acceptable Outcomes		
A 5.7	Podium (up to 3 storeys) <ul style="list-style-type: none"> <li>Side setback: 3m</li> <li>Rear/other setback: 3m</li> </ul>	
A 5.8	Tower (up to 8 storeys) <ul style="list-style-type: none"> <li>Side setback: 4m</li> <li>Rear/other: 4m</li> </ul>	
A 5.9	Tower (9 storeys and above) <ul style="list-style-type: none"> <li>Side setback: 6m</li> <li>Rear/other: 6m</li> </ul>	



PLOT RATIO		
R-Codes	Replace	Remain
	Clause A 5.10 replaces Clause A 2.5.1 of the R-Codes Volume 2.	-
Acceptable Outcomes		
A 5.10	No requirement.	



## 4.6 DEVELOPMENT INCENTIVES FOR COMMUNITY BENEFIT

Additional height stated under clause 4.5 may be considered depending on the extent of community benefit provided by a proposed development. This is discretionary and would only apply when the development achieves the development requirements set out below.


To calculate the additional discretionary height, the following is undertaken in order:

- a. The proposal is assessed against, and must satisfy, all Mandatory Criteria.
- b. The proposal is assessed against the Additional Criteria, listed below, and must achieve 50 points to be considered for 2 additional storeys above the acceptable height; or 100 points to be considered for the maximum height.
- c. Where a proposal includes Priority One criteria, this must be satisfied or demonstrate that there is an alternative. Where Priority One criteria is not applicable to the site the proposal may propose a combination of Priority Two and Three criteria.
- d. The proposal is assessed against the Vision, Development Objectives and Sub-Precinct Statements of Intent to ensure that the additional height and community benefits do not contradict the intent of this Policy.
- e. The proposal is means-tested against the City's Long Term Financial Plan to ensure that the City is financially capable of supporting the whole-of-life costs of proposed new or upgraded community infrastructure items.
- f. The decision-maker determines appropriate conditions to ensure the proposal delivers the requirements of the additional and mandatory criteria.



MANDATORY CRITERIA		
1.	A transport analysis supports the additional vehicular movements generated by the proposal. The analysis also includes enhancement of pedestrian and cycle movement within and to the development.	
2.	The development meets the energy efficiency requirements as set out in clause 4.4.15 of this Policy.	
3.	The additional height mitigates adverse impacts to adjoining properties with regard to solar access of outdoor living areas, major openings, solar collectors or spaces such as alfresco areas, outdoor dining and pedestrian arcades.	
4.	A servicing analysis supports the additional demand on infrastructure.	
5.	Retention and enhancement of places of heritage significance (Aboriginal or European) that may be located on the development site or immediately adjacent.	
6.	Provision of landscaping beyond the requirements of this Policy. This includes: <ul style="list-style-type: none"> <li>• Providing 5 percent more deep soil area above what is required under clause 4.4.12 of this Policy; or</li> <li>• Providing 10 percent more on structure planting above what is required under clause 4.4.12 of this Policy; and</li> <li>• Providing double the amount of trees required by Clause A3.3.5 of the R-Codes Volume 2. The additional landscaping is to feature advanced planting on both the podium as well as the storeys above, with evidence of the ability for this to grow and be sustained.</li> </ul>	
Additional Criteria - Priority One		Points
1.	<p>Applicant has entered a contract providing commercial space with subsidised rent for a period of no less than 10 years for a registered enterprise within the creative arts and cultural industries.</p> <p>The commercial space that is the subject of this community benefit must continue to operate as a use within the creative arts industry as listed below.</p> <p>The creative arts industry includes:</p> <ul style="list-style-type: none"> <li>• Arts and crafts</li> <li>• Designers, makers, and fabrication</li> <li>• Designer fashion</li> <li>• Education and civic</li> <li>• Film</li> <li>• Galleries</li> <li>• Interactive leisure software</li> <li>• Music</li> <li>• Performing arts</li> <li>• Publishing</li> <li>• Social enterprise</li> <li>• TV and radio</li> </ul> <p>At the discretion of the City, applicants can justify other sectors that focus on producing and promoting creative works, products, and services that are designed to entertain, educate, and inspire people.</p>	<p>Spaces 15sqm to 50sqm receive 30 points</p> <p>Spaces 51sqm to 100sqm receive 40 points</p> <p>Spaces over 100sqm receive 50 points</p>
2.	<p>Character buildings, identified through the Urban Design Study, are retained integrated and celebrated within the development, with the support of the Design Review Panel.</p> <p>The applicant is to demonstrate why a particular building is significant and should be retained.</p>	50

3.	<p>Provide a pedestrian laneway at a minimum width of 4m. The provision of a pedestrian laneway is to provide links between the streets listed below and is to be supported by active ground floor uses. Additional Criteria 1 is only available to the lots:</p> <ul style="list-style-type: none"> <li>• Bounded by Newcastle Street, Golding Street, Old Aberdeen Place and Charles Street;</li> <li>• Between Golding Street and Cleaver Street;</li> <li>• Between Cleaver Street and Tandy Street;</li> <li>• Between Tandy Street and Macvean Lane; and</li> <li>• Between Macvean Lane and Douglas Street.</li> </ul> <p>The location of the pedestrian laneways shall be creatively designed by the applicant, with the support of the Design Review Panel.</p> <p>Laneways shall:</p> <ul style="list-style-type: none"> <li>• Be designed with pedestrians in mind.</li> <li>• Provide comfortable seating to encourage people to stop and stay awhile.</li> <li>• Include landscaping to soften the urban environment and create a more pleasant atmosphere.</li> <li>• Provide lighting to enhance safety and create an inviting atmosphere.</li> <li>• Consider artwork and murals to make the laneway more interesting and engaging.</li> <li>• Include active land uses that address the laneway.</li> <li>• Support the ability to host events and activities.</li> </ul>	50
<b>Additional Criteria - Priority Two</b>		<b>Points</b>
4.	<p>Public or Community infrastructure improvements in the form of streetscape improvements, transport improvement, public open space enhancement, community space and contribution to individual infrastructure item with evidence that the infrastructure is needed and supported within proximity to the development, at the discretion of the City. Forms of evidence include a developer led Community Needs Assessment.</p> <p>The applicant is advised to refer to 05 The Public Realm - Place Plan to understand which actions are applicable.</p>	10 points per action delivered
<b>Additional Criteria - Priority Three</b>		<b>Points</b>
5..	Applicant has entered into a contract to deliver a minimum 10 percent affordable dwellings in partnership with an approved housing provider or not-for-profit organisation recognised by the Housing Authority.	50
6.	<p>Providing universal access dwellings as follows:</p> <ul style="list-style-type: none"> <li>• 15 per cent of all dwellings, across a range of dwelling sizes, meet Gold Level requirements as defined in the Liveable Housing Design Guidelines (Liveable Housing Australia); or</li> <li>• 8 per cent of dwellings are designed to Platinum Level as defined in the Liveable Housing Design Guidelines (Liveable Housing Australia).</li> </ul> <p>Or</p> <p>A dwelling type identified as a priority by the local government, such as aged and dependent dwellings, one-bedroom apartments, key-worker dwellings or other innovative housing models with evidence that the dwelling type is needed and supported.</p>	30
7.	Providing 5 percent of the site area as public open space, in addition to and pursuant to the requirements of clause 4.4.17.	50
8.	Provision of energy efficiency infrastructure that goes beyond the requirements as set out under clause 4.4.15 of this Policy. To be considered the development must meet a one star above the current Green Star rating or equivalent.	30



## 4.7 PERCENT FOR ART

Developers are responsible for providing art in line with the key strengths and characteristics of the areas in which they develop, as outlined in the City's Percent for Art Policy.

To build on the strengths of the existing creative makers and innovative businesses that inhabit the Pickle District and contribute to its unique sense of place, public art projects delivered through the percent for art scheme within the PDPF area shall prioritise the provision of cultural infrastructure. Where a public art project does not propose the provision of cultural infrastructure, the proposal must demonstrate how it addresses the Vision, Development Objectives and Ten Principles of Good Design. Should these be addressed to the satisfaction of the City, the proposal would be assessed in line with the City's Percent for Art Policy.





# 05 THE PUBLIC REALM - PLACE PLAN

The City of Vincent Town Centre Place Plans have been developed as a set of 'place-based' strategic action plans to guide the allocation of funding and resources in the City's town centres and districts. The Place Plans direct the City's service units to deliver a range of place-based initiatives and enable the City to effectively support and coordinate change.

The Place Plan will guide the implementation of all major initiatives in the PDPF area.

The Place Plan enables the range of initiatives identified in the City's suite of informing strategies and plans to be filtered, prioritised and resourced appropriately.

Some of the City's informing strategies and plans provide high level guidance for the direction and type of initiatives the City should be undertaking, while others provide specific actions.

In addition, all projects align with the outcomes of community engagement undertaken across all City projects.

All of the projects and initiatives being undertaken in the PDPF area are listed as 'actions'. Each action is explained using a three step process:

- Action
- Rationale
- Delivery

Also included is the timing, estimated required budget and lead:

- **Timeframe:** Represents when the action is likely to be commenced. This is subject to change and dependent on resourcing and funding opportunities as per the IPRF.
- **Lead:** Outlines who is responsible for the delivery and/or funding of the action. This can be the City, the Community and/or Private (developer through Development Incentives for Community Benefit).
- **Budget:** Estimates are included for the delivery of each action.
- **Source:** Outlines potential funding sources including FTE resourcing costs, internal funding through capital and/or operational expenditure, and/or external funding opportunities through private development, community benefit, cash in lieu payments and grant funding.

The Place Plan actions have been organised as per the six priorities of the City's Strategic Community Plan.

These include:

- ENHANCED ENVIRONMENT
- ACCESSIBLE CITY
- CONNECTED & HEALTHY COMMUNITY
- THRIVING PLACES
- SENSITIVE DESIGN
- INNOVATIVE & ACCOUNTABLE

The Place Plan highlights the broad range of projects and initiatives the City is undertaking to support and improve the PDPF area.


The Implementation Framework sets out the actions, and the delivery of these.

The Place Plan considers the City's Community and Stakeholder Engagement Strategy guiding principles:

- Make well informed decisions that are supported by evidence, aligned with strategic direction, and based on the needs and interests of everyone involved.
- Hear and understand our community.
- Meaningfully include the community in the decision-making process.
- Engage in a way that facilitates the involvement of impacted communities.
- Communicate before, during and after a decision is made.

Town centres are complex. By engaging meaningfully, the City will maximise the opportunity to understand what is important to the community and stakeholders and make informed decisions that are aligned with the City's key strategies. In addition, all projects identified in the Place Plan align with outcomes from the extensive community engagement program undertaken during the drafting of the PDPF.

The City will undertake additional community engagement in line with the City's Community and Stakeholder Engagement Strategy on a number of projects in the Place Plan. These projects are indicated by the following icon:



## 5.1 ENHANCED ENVIRONMENT

Sets out the actions and projects which assist the City to make the best use of our natural resources for the benefit of current and future visitors, residents, and businesses of the Pickle District.

### ACTION 5.1.1 DESIGN AND IMPLEMENT IMPROVEMENTS TO THE PICKLE PARK.


<b>Rationale</b>	The verge along Old Aberdeen Place is in close proximity to the Graham Farmer Freeway and features a number of established trees and shrubs, but is not maintained to a high standard consisting of weeds and loose rocks.		
	This presents the opportunity to improve the design, planting and maintenance on the verge and make it a usable space for the public, supporting local events and community initiatives such as the town team's popular art crawls. It will also act as a billboard for the district with the site's high visibility from the freeway.		
	Works will include but are not limited to landscaping, planting, seating, shade, public art, bike racks, power access and water access.		
<b>Delivery</b>	This action aligns with The Pickle District Town Team's Action Plan (Proposition Three and Action 3) to increase vegetation and landscape the area to transform it into a community space.		
	Work with the town team to develop and implement a design for Pickle Park along the Old Aberdeen Place verge.		
	Timeframe:	2023/24-2024/25	Lead: City / Community
	Budget:	\$30,000	Source: Internal / External

### ACTION 5.1.2 ENCOURAGE UPTAKE IN BUSINESS COMMUNITY SOLAR WITH DISTRIBUTION OF PROMOTIONAL VIDEO.

<b>Rationale</b>	Current uptake of solar in the business community is low compared to the residential sector. This is primarily due to owners of the properties not being the operator who receives the power bill. Options for tenants are currently limited and in all cases need the building owner's cooperation and permission to proceed.		
	There are a number of options available that will be communicated to business owners and building owners for them to mutually benefit through the installation of solar.		
<b>Delivery</b>	Develop promotional material communicating the options available to business and building owners to mutually benefit through the installation of solar, and distribute through existing communications networks.		
	Timeframe:	2023/24	Lead: City
	Budget:	\$500	Source: Internal

### ACTION 5.1.3 INCREASE USABILITY OF SUTHERLAND RESERVE.

<b>Rationale</b>	As outlined in the context section 2.3.1, the Pickle District lacks in public open space. The only existing green space within the district is Sutherland Reserve, tucked into the western corner.		
	Sutherland Reserve is protected from the busy intersection adjacent and resultant noise and fumes by its lower grade and large perimeter trees. However, use of the reserve is low as it lacks amenity and feels unsafe at night.		
	There is an opportunity to increase the usability of Sutherland Reserve in alignment with the Public Open Space Strategy. Upgrades can include but are not limited to seating, water fountain, shade, bike rack, lighting.		
<b>Delivery</b>	The City will develop a plan to determine a program of amenity upgrades of existing facilities and the provision of additional facilities that could be added to the park in the future. It is anticipated that upgrades identified can be delivered by developers seeking development incentives for community benefit.		
	<b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will have the opportunity to contribute towards reserve upgrades from the City's plan.		
	Timeframe:	2025/26 onwards	Lead: City / Private
	Budget:	\$80,000	Source: Internal / External





**ACTION 5.1.4 IMPROVE URBAN CANOPY.**

<p><b>Rationale</b></p>	<p>Canopy cover plays an important role in creating walkable and liveable neighbourhoods and encouraging people to linger longer.</p> <p>The Pickle District’s urban canopy is very low. Some mature trees can be found around the perimeter, particularly at Sutherland Reserve and the Old Aberdeen Place verge, but the streets throughout are severely lacking. Some young trees were recently planted along Cleaver and Golding Streets as part of the street upgrades.</p> <p>The Pickle District is included in Western Power’s Vincent Underground Power Project, West Perth Project Area 1190, where the remainder of the district will be under grounded. Detailed design is anticipated to occur in 2025 and construction in 2027. This will present opportunities to allow additional street tree planting and for trees to mature and canopy to without the restriction of power lines.</p> <p>The City will develop an Urban Forest Plan for the PDPF area that will:</p> <ul style="list-style-type: none"> <li>• Review existing challenges in establishing mature trees with canopy coverage in the built environment;</li> <li>• Recommend suitable tree species; and</li> <li>• Identify tree planting opportunities in median strips, verge, footpath and parking areas.</li> </ul>								
<p><b>Delivery</b></p>	<p>The City will develop and implement an Urban Forest Plan to improve the tree canopy in the Pickle District and surrounding residential streets. It is anticipated that actions identified in the Urban Forest Plan will be delivered by developers seeking development incentives for community benefit.</p> <p><b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b>          Developers will have the opportunity to contribute towards actions in the City’s Urban Forest Plan for the PDPF area.</p> <table border="1" data-bbox="1662 1312 2843 1430"> <tr> <td>Timeframe:</td> <td>2026/27 onwards</td> <td>Lead:</td> <td>City</td> </tr> <tr> <td>Budget:</td> <td>\$20,000 (Plan)</td> <td>Source:</td> <td>Internal</td> </tr> </table>	Timeframe:	2026/27 onwards	Lead:	City	Budget:	\$20,000 (Plan)	Source:	Internal
Timeframe:	2026/27 onwards	Lead:	City						
Budget:	\$20,000 (Plan)	Source:	Internal						

## 5.2 ACCESSIBLE CITY

Sets out the actions and projects which enhance connectivity, improve the use of public transport, deliver parking efficiencies, and create a more pedestrian and cycle friendly Pickle District.



### LEGEND

- ACTION 5.2.1 MAIN STREET UPGRADES
- ACTION 5.2.2 AND 5.2.4
- BUS STOPS
- TRAIN STATION
- PEDESTRIAN CROSSINGS
- PUBLIC OPEN SPACE
- EXISTING LANEWAY
- SAFE ACTIVE STREETS
- PRIMARY BIKE ROUTE
- FOOTPATHS
- BUS ROUTES
- FREE TRANSIT BUS ROUTE
- 400 METRE RADIUS
- PRECINCT BOUNDARY

### ACTION 5.2.1 DEVELOP AND IMPLEMENT MAIN STREET UPGRADES.

<b>Rationale</b>	<p>The Pickle District does not have a traditional main street and lacks amenities found in the City's town centres including shade, landscaping, public art, lighting and street furniture. As the Pickle District transforms and land uses evolve, streetscape improvements are required to meet the needs of local businesses, residents and visitors.</p> <p>Cleaver Street is the main arterial road with high visibility. Cleaver Street was upgraded in 2021. Upgrades included road resurfacing, new line marking, new curbing, tree planting along verges and the median, and the installation of pathway nibs or 'artlets' to host public art. Cleaver street presents the opportunity to be enhanced by further streetscape upgrades to visually represent it as a main street of the Pickle District. Additionally, Old Aberdeen Place is emerging as a gathering place with creative businesses fronting onto the street and the upcoming Pickle Park project.</p> <p>Improved public amenities are required to establish Cleaver Street and Old Aberdeen Place as main streets and set them apart from the standard streets in the area. This includes road resurfacing, lighting, landscaping, street furniture and opportunities for public art including conduits laid for connection to power.</p>			
	<p>The City will develop a plan to improve and implement increased public amenity on Cleaver Street and Old Aberdeen Place. It is anticipated that upgrades identified can be delivered by developers seeking development incentives for community benefit.</p>			
<b>Delivery</b>	<p><b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will have the opportunity to contribute towards main street upgrades from the City's plan.</p>			
	Timeframe:	2025/26 onwards	Lead:	City / Private
	Budget:	\$60,000 (Plan)	Source:	Internal / External

### ACTION 5.2.2 INVESTIGATE PEDESTRIAN AND CYCLIST CONNECTION BETWEEN LOFTUS STREET AND DRUMMOND PLACE.

<b>Rationale</b>	<p>Drummond Place terminates with a cul-de-sac travelling west, approximately 15 metres from the Loftus Street shared path. There is currently a sandy and steep verge which is difficult to traverse and no formal connection has been established.</p> <p>A connection here for pedestrians and cyclists would greatly improve accessibility and connectivity between the Pickle District and the Leederville Town Centre. Further connection to the PSP at Old Aberdeen Place should also be considered in the future.</p>			
	<p>Investigate options to create a connection for pedestrians and cyclists between the Loftus Street and Drummond Place and advocate for implementation of solutions to State Government and other relevant organisations.</p>			
<b>Delivery</b>	Timeframe:	2023/24 onwards	Lead:	City
	Budget:	\$0	Source:	FTE



**ACTION 5.2.3 DEVELOP AND IMPLEMENT A PLAN TO IMPROVE PEDESTRIAN EXPERIENCE.**

<b>Rationale</b>	The walkability of the area is poor due to inconsistent path widths and a severe lack of shade. Improvements to the pedestrian experience will create a sense of place and identity, encourage people to linger longer and support the local businesses and growing economy.		
	With the undergrounding of power anticipated to be completed in 2028 (West Perth Project Area 1190 in Western Power's Vincent Underground Power Project), this will allow opportunities to reduce footpath clutter and upgrade lighting, improving the walkability of the Pickle District.  Improvements to the pedestrian experience should address paths, tree planting and shade.		
<b>Delivery</b>	The City will identify required improvements to the pedestrian experience and develop a plan for delivery. It is anticipated that improvements identified can be delivered by developers seeking development incentives for community benefit.		
	<b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will have the opportunity to contribute towards pedestrian experience upgrades from the City's plan.		
	Timeframe:	2025/26-2026/27	Lead: City / Private
	Budget:	\$50,000 (Plan)	Source: Internal / External

**ACTION 5.2.4 INVESTIGATE FEASIBILITY OF DRUMMOND PLACE UNDERPASS.**

<b>Rationale</b>	Loftus Street is a major impediment to pedestrian movement, particularly between Leederville Town Centre and the Pickle District.		
	An underpass for pedestrians and cyclists would provide a safe route without the interruptions of heavy traffic and intersections. It would also leverage the vibrant and active Leederville Town Centre by encouraging patrons to walk across to the Pickle District.		
<b>Delivery</b>	Investigate the feasibility of an underpass to connect Drummond Place to Leederville for pedestrians and cyclists, and advocate for exploration of opportunities to State Government and other relevant organisations.		
	Timeframe:	2024/25 onwards	Lead: City
	Budget:	\$0	Source: FTE

**ACTION 5.2.5 IMPLEMENT VINCENT WAYFINDING SIGNAGE PLAN.**

<b>Rationale</b>	Wayfinding is a critical component to the legibility and walkability of a place. It helps people determine how to move through spaces, guided by architecture, urban design, landmarks and views.		
	Wayfinding in Vincent has significant room for improvement. An over proliferation of signage and styles competes for attention and can result in confusion.  The Vincent Wayfinding Signage Plan has been prepared and will be implemented to: <ul style="list-style-type: none"> <li>• Create a comprehensive, clear and consistent visual communication system with concise messaging;</li> <li>• Only include the information that is relevant to the space, location and navigation path; and</li> <li>• Focus on active transportation mode users, particularly pedestrians and cyclists.</li> </ul>		
<b>Delivery</b>	Implement the Vincent Wayfinding Signage Plan in the Pickle District and investigate additional branding opportunities.		
	<b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will have the opportunity to contribute towards the delivery of the City's Wayfinding Signage Plan.		
	Timeframe:	2023/24-2025/26	Lead: City / Private
	Budget:	\$50,000	Source: Internal / External



## 5.3 CONNECTED & HEALTHY COMMUNITY

Sets out the actions and projects which contribute to the Pickle District's unique sense of place, and encourage the community to connect with each other to enhance their quality of life.

### ACTION 5.3.1 SUPPORT LOCAL TOWN TEAM AND COMMUNITY TO DELIVER ACTIVATION AND COMMUNITY INITIATIVES IN THE PICKLE DISTRICT.

<b>Rationale</b>	Feedback collected through stakeholder engagement showed strong support for community initiatives, activations and events in the area.		
	The Pickle District is fortunate to have an active town team that advocate for the area as an arts precinct, and are known for their creative events that draw visitation. It is important to continue to support the local town team, businesses and community to deliver activations and initiatives in order to provide opportunities for the community to connect with place, each other, local businesses and arts and cultural experiences.		
<b>Delivery</b>	Continue to support the local town team and community to deliver activation and community initiatives through the Town Team Grant and Festivals & Events Sponsorship annual funding programs.		
	Timeframe:	2023/24 onwards	Lead: City / Community
	Budget:	\$10,000 p.a.	Source: Internal



## 5.4 THRIVING PLACES

Sets out the actions and projects which assist the City to create, enhance, and promote great places and spaces in the Pickle District in order for it to reach its activation and economic potential.



Arts, Culture and Activation

### LEGEND

- ACTION 5.4.1 ARTLET LOCATIONS
- ACTION 5.4.4 DISTRICT GATEWAYS
- ▤ ACTION 5.4.2 PEDESTRIAN LANEWAY
- PUBLIC OPEN SPACE
- - - 400 METRE RADIUS
- PRECINCT BOUNDARY
- 🎨 ART STUDIO
- 🖼️ ART GALLERY
- 🎬 CINEMA
- 🎪 EVENTS
- ☕ CAFE
- 🎤 LIVE MUSIC VENUE

### ACTION 5.4.1 COLLABORATE WITH THE PICKLE DISTRICT TOWN TEAM TO IMPLEMENT ART FOR ARTLETS.

<b>Rationale</b>	<p>The arrival of creative businesses and their involvement in the local town team over recent years has seen the Pickle District organically emerge as an inner city arts precinct. The town team are well placed to define the artistic vision for the area and contribute towards curation and delivery of public artworks.</p> <p>There is an opportunity to work with the town team to curate and deliver public artworks on concrete nib 'artlets' located along Cleaver Street.</p> <p>This action aligns with the Pickle District Town Team's Action Plan (Proposition Two, Actions 6 and 12), which identifies the opportunity to experiment with design and art ideas to improve Cleaver Street.</p>		
<b>Delivery</b>	<p>The City will collaborate with The Pickle District Town Team to curate and deliver public artworks for the Cleaver Street artlets. Developers will have the opportunity to contribute funding towards the public art project through the development incentives for community benefit and through the percent for art scheme.</p> <p><b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will be have the opportunity to contribute towards the public art projects for artlets.</p>		
	Timeframe:	2023/24-2025/26	Lead: City / Community
	Budget:	\$120,000	Source: Internal / External



**ACTION 5.4.2 EXPLORE OPPORTUNITIES FOR PEDESTRIAN LANEWAYS BETWEEN DOUGLAS STREET AND CLEAVER STREET.**

<b>Rationale</b>	Creative businesses in the Pickle District are located in two main clusters, centred around Douglas Street and Cleaver Street. The pedestrian experience between the two locations is currently poor and indirect.		
	The opportunity exists to provide pedestrian laneway connectivity between Douglas Street and Cleaver Street. This will support the emerging arts scene and local businesses in the district, as well as create additional spaces for the facilitation of events and activations.		
	This action aligns with the Pickle District Town Team's Action Plan (Proposition One, Action 11) which calls for laneway activation to connect art and experiences.		
<b>Delivery</b>	The City will facilitate discussion with property owners and developers of the relevant sites to investigate pedestrian laneways connecting Douglas Street through to Cleaver Street. Developers seeking development incentives for community benefit will have the opportunity to deliver the pedestrian laneways.		
	<b>Development Incentives for Community Benefit, Additional Criteria 3 - Priority One</b> To be delivered by developers of relevant sites.		
	Timeframe:	2024/25 onwards	Lead: Private
	Budget:	As per 4.6	Source: External

**ACTION 5.4.3 IMPLEMENT PICKLE DISTRICT GATEWAYS**

<b>Rationale</b>	Gateways mark the entrance to an area for visitors and are the first established memory of a place. They represent it's character, personality and provide a sense of community.		
	The Vincent Wayfinding Signage Plan proposes to formalise gateways to precincts and town centres with collocated signage and public artwork. The map on the previous page outlines the locations of the proposed gateways for the Pickle District.		
	This action aligns with the Pickle District Town Team's Action Plan (Proposition Three, Action 4) which calls for laneway activation to connect art and experiences. Having built the arts precinct from scratch, the town team are well placed to define the artistic vision for the area and contribute towards curation and procurement of public artworks.		
<b>Delivery</b>	The City will engage with The Pickle District Town Team to procure public artworks for the district gateways in alignment with the Wayfinding Signage Plan. Developers will have the opportunity to contribute funding towards the public art projects through the development incentives for community benefit and through the percent for art scheme.		
	<b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will have the opportunity to contribute towards implementation of district gateways and public art for relevant developments.		
	Timeframe:	2025/26-2027/28	Lead: City / Community / Private
	Budget:	\$250,000	Source: Internal / External





ACTION 5.4.4 RETAIN CREATIVE INDUSTRY			
Rationale	Feedback from community and targeted stakeholder engagement shows overwhelming support for the burgeoning arts scene in the Pickle District, founded and grown by the local businesses and town team.		
	Development of the precinct poses a threat to the creative businesses that make the vibrant arts hub, potentially losing tenancies due to building works and/or becoming priced out of leases.		
	The Making Space for Culture report identified this threat as a major opportunity to work with the private sector to retain spaces for the creative industry. This action seeks to do so through planning mechanisms including community benefit incentive and percent for art contributions.		
Delivery	The City will facilitate discussion with property owners and developers to provide cultural infrastructure in the Pickle district through development incentives for community benefit and percent for art contributions.		
	<b>Development Incentives for Community Benefit, Additional Criteria 1 - Priority One and Percent for Art</b>		
	Developers will have the opportunity to provide tenancies for creative businesses, and to prioritise the provision of cultural infrastructure through percent for art contributions.		
	Timeframe:	2023/24 onwards	Lead:
Budget:	As per 4.6	Source:	External

ACTION 5.4.5 SUPPORT THE IMPLEMENTATION OF THE VIBRANT PUBLIC SPACES POLICY				
Rationale	Vibrant public spaces are areas in the public realm that support social interaction and community engagement. They are spaces which provide pedestrian amenity and are for everyone to enjoy. Vibrant public spaces are dog friendly and smoke free at all times.			
	The Vibrant Public Spaces policy seeks to facilitate public and private investment in the public realm for the benefit of the community.			
	The City's Place team can take a stewardship role to guide the implementation of various actions under the policy, whether undertaken by the City or by private landowners or business owners.			
Delivery	Support the implementation of the Vibrant Public Spaces policy in the Pickle District.			
	Timeframe:	2023/24 onwards	Lead:	City
	Budget:	\$0	Source:	FTE




## 5.5 SENSITIVE DESIGN

Sets out the actions and projects which assist the City to encourage unique, high quality developments that respect and respond to the character and identity of the Pickle District.

### ACTION 5.5.1 DEVELOP AND IMPLEMENT STREETScape STYLE GUIDE

Rationale	The Pickle District streetscape requires upgrading. As the precinct enters into an age of redevelopment, the opportunity exists to deliver consistent streetscapes and enhance the character and sense of place.		
	The City's Accessible City Strategy was developed using the Link and Place Framework. Action 2.2.1 is to 'Develop a set of Link and Place Guidelines to guide future streetscape improvements.'		
	Whilst this action will apply to the City as a whole, there is an opportunity to build upon the guidelines to develop a streetscape style guide specific to the Pickle District. This will ensure future investment in the public realm is consistent and creates a sense of place through developing a colour and materials palette, a suite of street furniture and appropriate landscaping elements to be applied throughout the Precinct.		
Delivery	The City will develop and implement a streetscape style guide for the Pickle District.		
	The guide will then be used to guide streetscape upgrades that form part of the City's program of works as well as those that arise as the result of new development.		
	<b>Development Incentives for Community Benefit, Additional Criteria 4 - Priority Two</b> Developers will have the opportunity to provide streetscape upgrades and implementation in line with the City's streetscape style guide. This will be based on a needs analysis done for the public realm adjacent to or most closely servicing each development.		
	Timeframe:	2024/25-2025/26	Lead:
Budget:	\$80,000	Source:	Internal / External



## 5.6 INNOVATIVE AND ACCOUNTABLE

Sets out the actions and projects which assist the City to support the community to realise its vision. To achieve this, we will be an organisation that manages resources well, communicates effectively, and takes our stewardship role seriously.

ACTION 5.6.1 INVESTIGATE OPPORTUNITIES FOR BUSINESS ENHANCEMENT GRANTS			
<b>Rationale</b>	The public realm and visitor experience of the City's places are informed by both public and the privately owned land, buildings and the businesses that inhabit them.		
	Enhancements to public land, including planter boxes, parklets, wayfinding signage, bike racks and other street furniture is facilitated through Place Plans and the Vibrant Public Spaces Policy.		
	To date, there has been no direct avenue to provide financial support to business owners and landlords to make incremental improvements of this nature to privately owned land and buildings.		
<b>Delivery</b>	Business enhancement grants are a cost-effective way to partner with small businesses and spark small-scale incremental improvements that enhance the street appeal, presentation and attractiveness of our town centres and places.		
	Investigate development and implementation of a Business Enhancement Grant in the City of Vincent.		
	Timeframe:	2024/25 onwards	Lead: City
	Budget:	\$10,000	Source: Internal

ACTION 5.6.2 INVESTIGATE OPPORTUNITIES FOR PLACE IMPROVEMENT FUNDING			
<b>Rationale</b>	Vincent's vibrant places and spaces are integral to our identity, economy and appeal. We want to create, enhance and promote great places and spaces for everyone to enjoy.		
	Funding place-based projects is challenging in local governments with limited budgets and high asset renewal costs.		
	The City's seeks various funding partnerships and grants to support the delivery of place-based projects and trialling new initiatives aligned with town centre place plans.		
<b>Delivery</b>	The opportunity exists to investigate the feasibility of implementing different funding approaches to support ongoing delivery of place-based programs and projects.		
	Investigate different funding approaches to support ongoing delivery of place-based programs and projects.		
	Timeframe:	2023/24 onwards	Lead: City
	Budget:	\$0	Source: FTE

ACTION 5.6.3 SEEK FUNDING OPPORTUNITIES FROM THE PERTH PARKING LEVY			
<b>Rationale</b>	Vincent's vibrant places and spaces are integral to our identity, economy and appeal. We want to create, enhance and promote great places and spaces for everyone to enjoy.		
	The Pickle District lies within the Perth Parking Management Area (PPMA) resulting in the City and some private land holders making annual contributions to the Perth Parking Levy (PPL). This Levy is used to fund balanced transport initiatives within the PPMA that support reduced private vehicle use and promote vibrant, active places.		
	The PPL and distribution of levy funds is administered by the Department of Transport (DOT). There is an opportunity for the City to advocate for transport and public realm improvement projects to the DOT for funding consideration.		
<b>Delivery</b>	Advocate for funding from the Perth Parking Levy and other funding opportunities to deliver transport improvements and improvements that provide economic benefit or improve the public realm in the Pickle District.		
	Timeframe:	2024/25 onwards	Lead: City
	Budget:	\$0	Source: FTE



## 5.7 IMPLEMENTATION FRAMEWORK

KEY ACTION / PROJECT		BUDGET	LEAD	RESPONSIBLE TEAM	SUPPORT TEAM	TIMING				
						23/24	24/25	25/26	26/27	27/28
<b>ENHANCED ENVIRONMENT</b>										
5.1.1	Design and implement improvements to the Pickle Park.	\$30,000	City / Community	S&D	I&E	✓	✓			
5.1.2	Encourage uptake in business community solar with distribution of promotional video.	\$500	City	S&D	C&B	✓				
5.1.3	Increase usability of Sutherland Reserve.	\$80,000	City / Private	S&D	I&E			✓	✓	✓
5.1.4	Improve urban canopy.	\$40,000	City	S&D	I&E				✓	✓
<b>ACCESSIBLE CITY</b>										
5.2.1	Develop and implement main street upgrades.	\$60,000	City / Private	S&D	I&E			✓	✓	✓
5.2.2	Investigate pedestrian and cyclist connection between Loftus Street and Drummond Place.	\$0	City	S&D	I&E	✓	✓	✓	✓	✓
5.2.3	Develop and implement a plan to improve pedestrian experience.	\$50,000	City / Private	S&D	I&E			✓	✓	
5.2.4	Investigate feasibility of Drummond Place underpass.	\$0	City	S&D	I&E		✓	✓	✓	✓
5.2.5	Implement Vincent Wayfinding Signage Plan.	\$50,000	City / Private	I&E	S&D	✓	✓	✓		
<b>CONNECTED AND HEALTHY COMMUNITY</b>										
5.3.1	Support local town team and community to deliver activation and community initiatives in the Pickle District.	\$10,000 p.a.	City / Community	C&B	S&D	✓	✓	✓	✓	✓
<b>THRIVING PLACES</b>										
5.4.1	Collaborate with The Pickle District Town Team to implement art for artlets.	\$120,000	City / Community	S&D	I&E	✓	✓	✓		
5.4.2	Explore opportunities for pedestrian laneways between Douglas Street and Cleaver Street.	As per 4.6	Private	S&D	I&E		✓	✓	✓	✓
5.4.3	Implement Pickle District gateways.	\$250,000	City / Community / Private	S&D	I&E			✓	✓	✓
5.4.4	Retain creative industry.	As per 4.6	Private	S&D	I&E	✓	✓	✓	✓	✓
5.4.5	Support the implementation of the Vibrant Public Spaces Policy.	\$0	City	S&D	I&E	✓	✓	✓	✓	✓
<b>SENSITIVE DESIGN</b>										
5.5.1	Develop and implement streetscape style guide.	\$80,000	City / Private	S&D	I&E		✓	✓		
<b>INNOVATIVE &amp; ACCOUNTABLE</b>										
5.6.1	Investigate opportunities for business enhancement grants.	\$10,000	City	S&D	C&B		✓	✓	✓	✓
5.6.2	Investigate opportunities for place improvement funding.	\$0	City	C&B	S&D	✓	✓	✓	✓	✓
5.6.3	Seek funding opportunities from the Perth Parking Levy.	\$0	City	S&D	C&B	✓	✓	✓	✓	✓



CITY OF VINCENT

**Administration and Civic Centre**

**A:** 244 Vincent St, Leederville WA 6007

**T:** 08 9273 6000

**E:** [mail@vincent.wa.gov.au](mailto:mail@vincent.wa.gov.au)

**W:** [vincent.wa.gov.au](http://vincent.wa.gov.au)



@cityofvincent



# Appendix 1: Pickle District Planning Framework

Servicing Report  
August 2023

# Table of Contents

- 1.0 Introduction 3
  - 1.1 Background 3
  - 1.2 Purpose of this report 3
  - 1.3 Location 3
  - 1.4 Scope and Limitations 4
  - 1.5 Assumptions 5
  
- 2.0 Servicing 5
  - 2.1 Water Reticulation 5
  - 2.2 Sewerage Reticulation 5
  - 2.3 Power Supply 5
  - 2.4 Telecommunications 6
  - 2.5 Gas 7
  
- 3.0 Public Authorities 7

## Figure Index

- Figure 1: Location of the Pickle District
- Figure 2: Pickle District Planning Framework

## Appendices

- Appendix 1: Water Corporation Information 8 - 14

# 1.0 Introduction

## 1.1 Background

The Pickle District Planning Framework (PDPF) has been prepared to guide development within the private realm and investigate actions to improve the public realm. The PDPF has been prepared under the provisions of Clause 9(2) of Schedule 2 of the Planning and Development (Local Planning Scheme) Regulations 2015 (the Regulations).

This framework will provide a comprehensive planning framework that will provide guidance on decision making for the planning and development of the Pickle District (the Precinct).

## 1.2 Purpose of this report

This report provides information on the existing and proposed servicing infrastructure to support the preparation of a Local Planning Policy for the Precinct

## 1.3 Location

The Precinct is located north west of the Perth CBD. It is bounded by the Graham Farmer freeway to the south, Loftus Street to the west, Charles Street to the east and includes properties to the North of Newcastle Street (Figure 1). The precinct includes the suburbs of West Perth.




Figure 1. Location of the North Claisebrook Precinct in relation to the City's local government area.





Figure 2. Pickle District

## 1.4 Scope and Limitations

The following servicing infrastructure were investigated in this report

- Water Reticulation
- Sewer Reticulation
- Power
- Telecommunications
- Gas
- Water Corporate Main Drainage
- NBN Co

As part of this investigation, the following servicing authorities were contacted:

- NBN Co
- Water Corporation
- ATCO Gas

The following public authorities were also contacted

- Public Transport Authority
- City of Perth

This investigation is limited to the existing road reserves within the study area and excludes underground infrastructure located within private lots.

## 1.5 Assumptions

This servicing report is based on the Pickle District included in Figure 2. The City is to provide zoning and maximum land use information, so that this can be conveyed to the agencies when making enquiries regarding servicing strategy and proposed infrastructure (to be supplied at the next report revision).

## 2.0 Servicing

### 2.1 Water Reticulation

#### Existing Infrastructure

There are several Water Corporation assets within the precinct that service water, sewerage and draining within the precinct and to other areas.

A critical pipeline is located along the western portion of Drummond Place and diverges to run along Simpson Street. A risk assessment is required for all development adjacent to these streets.

A series of other pipes, ranging from 75mm to 150mm in diameter run throughout the precinct. The most common pipe type is cast iron (CI). The pipe are to be replaced upon redevelopment of each site.

### 2.2 Sewerage Reticulation

While there is an extensive sewer network that services lots within the study area, given the age of the area, there may be instances where existing development is serviced by septic tanks. Upon redevelopment, these septic tanks would be required to be decommissioned and connected to the reticulated sewer network. Typically this is addressed through conditions of subdivision or development approval.

### 2.3 Power Supply

Western Power infrastructure is present throughout the precinct, along Newcastle, Cleaver, Tandy, Douglas and Strathcona Streets. Power poles exist to support this overhead power and are located on all Streets within the precinct. Part of the Western Powers fibre network also exists within the precinct along Cleaver Street, deviating on Old Aberdeen Place.

Western Power infrastructure is generally protected by easements which are registered on the Certificates of Title. These easements, which can vary in width dependent on voltage and transmission pole spacing, generally provide for Western Power and it's contractors to access land for the purpose of constructing and maintaining electrical infrastructure on the land.

These easements may also restrict the activities that can be undertaken and/or the structures that can be placed within the easements. Accordingly, any development within registered easement areas require approval from Western Power.

Any augmentation costs of the distribution network will be the responsibility of the developer.

## 2.4 Telecommunications

### 2.4.1 Telstra

#### Existing Infrastructure

Telstra records indicate there are major cables and/or optic fibre in the area.  
A Certified Locating Organisation is required to identify the location of the asset/s.

### 2.4.2 TPG Telecom

#### Existing Infrastructure

TPG records indicate there are underground assets running to the West of the Precinct along Loftus Street.

### 2.4.3 Optus (WA)

Optus has a underground

### 2.4.4 Nextgen Group

#### Existing Infrastructure

Nextgen hold no assets within this precinct.

### 2.4.5 Vocus Group

#### Existing Infrastructure

Records indicated that there are underground assets running along Newcastle Street, Cleaver Street, Old Aberdeen Place, Douglas Street, Leederville Parade, Golding Street, Charles Street and Prospect Place.

### 2.4.6 Verizon

#### Existing Infrastructure

Verizon holds no assets within this precinct.

### 2.4.7 Optus (WA)

#### Existing Infrastructure

Records indicate that there are underground assets running the length of Newcastle Street.

### 2.4.8 NBN Co

#### Existing Infrastructure

NBN cables are run throughout the precinct connecting all lots to NBN Co infrastructure.

## 2.5 Gas

### Existing Infrastructure

The existing gas network is owned and operated by ATCO Gas. There is a critical gas line running along Loftus Street, to the west of the precinct. Gas lines run throughout the precinct

### Proposed Infrastructure

There may be a need for portions of the existing gas network to be upgraded to respond to ultimate development outcomes. Any reticulation mains upgrades is the responsibility of the developer.

## 3.0 Public Authorities

### 3.1 Public Transport Authority

The Disability Discrimination Act 1992 requires that all public bus stops must eventually comply with the Disability Standards for Accessible Public Transport 2002 (Disability Standards). Under section 32.1 of the Disability Standards, any party undertaking works which results in the substantial refurbishment or alteration of a bus stop passenger boarding area must rectify the passenger boarding area to achieve full compliance with the Disability Standards. All planned works or activities that may impact upon any of the areas or improvements detailed below will likely trigger this requirement:

- a bus stop passenger boarding area (i.e. the bus stop post and the area immediately near the bus stop where passengers wait to board a bus);
- a bus stop passenger boarding area kerb height (i.e. the height of the kerb relative to the road surface);
- a bus shelter or the hardstand area surrounding it; and/or
- a footpath or pedestrian pram ramp connecting a bus stop boarding area to the local footpath network.

If you are proposing to work within the PTA's Rail Reserve please be aware that a 3rd Party Access procedure applies. For more information about accessing the rail reserve please contact [PTAthirdpartyaccess@pta.wa.gov.au](mailto:PTAthirdpartyaccess@pta.wa.gov.au)

### 3.2 City of Perth

City of Perth holds no assets within this precinct.

# Appendix 1: Water Corporation

## Protecting Buried Pipelines Information Brochure



### Important information for any work near Water Corporation Pipelines

**Working on or near Water Corporation pipelines can be dangerous. At all times the safety of the general public and your employees for your works remains your responsibility.**

The information contained in this brochure is for asset protection advice only. For advice concerning personnel safety, please refer to the Annex attached

Pipeline damage can be expensive, hazardous and highly disruptive to the community. If you are a planner, constructor, supervisor, excavator or work in a similar role this brochure has important information to help you plan your site work and ensure that Water Corporation pipelines are not damaged.

**All buried pipes must be visually identified before using powered machinery.**

### About Water Corporation Pipelines

The Water Corporation operates vast water, sewerage and drainage pipe networks throughout WA. At any given location there may be multiple pipes in the ground of different sizes, depths, alignments and materials.

**Many pipes operate at high pressures and flow rates.** The sudden release of large volumes of water under pressure may be dangerous to people in the vicinity and could lead to significant damage and community disruption.

**Water reticulation mains** are present in most streets with individual property services connected to these mains. These property services may be located by finding the property water meter. Property services are not marked on plans, however their presence should be anticipated.

**Sewer Gravity Mains, Sewer Property Services and Drainage Gravity Mains** are present in many streets and are often within property boundaries. Gravity mains may be located by the presence of an access chamber or manhole along the line of the sewer. Sewer property services are not marked on plans however their presence should be anticipated. See "Private Property" below for more information.

**Other assets** associated with pipes are: anchor and thrust blocks, sampling points, valves, valve pits, cathodic protection systems, underground tanks, manholes, and flow measuring equipment.

Interfering with or damaging these assets can be hazardous. Some pipes operate at high pressures and volumes, and hazardous gases may be present.



*The Essential First Step.*

# Plan Legend (summary)

## INFORMATION BROCHURE



This legend is provided to [Dial Before You Dig](#) users to assist with interpreting Water Corporation plans. A more detailed colour version can be downloaded from [www.watercorporation.com.au](http://www.watercorporation.com.au). (Your business > Working near pipelines > Downloads)

**WARNING - Plans may not show all pipes or associated equipment at a site, or their accurate location. Pothole by hand to verify asset location before using powered machinery.**


	<p><b>WATER, SEWERAGE AND DRAINAGE PIPELINES</b></p> <p><b>CRITICAL PIPELINE (thick line) EXTRA CAUTION REQUIRED</b> A risk assessment may be required if working near this pipe. Refer to your <a href="#">Dial Before You Dig</a> information or call 131375.</p> <p>Pipes are not always labelled on plans as shown here – assume all pipes are significant and pothole to prove location and depth.</p> <p>P.M. pressure main M.S. main sewer R rising main (i.e. drainage pressure main)</p> <p><b>Common material abbreviations:</b> AC asbestos cement e.g. 100AC NOTE: AC is brittle and is easily damaged. CI cast iron GRP glass reinforced plastic P PVC - class follows pipe material (e.g.100P-12) RC reinforced concrete S steel VC vitrified clay</p>
	<p><b>NON-STANDARD ALIGNMENT</b> Pipes are not always located on standard alignments due to local conditions. (i.e. Other than 2.1 m for reticulation mains and 4.5 m for distribution mains.)</p>
	<p><b>OTHER PIPE SYMBOLS</b> Other numbers or codes shown on pipes are not physical attributes. These are Water Corporation use only.</p>
	<p><b>CONCRETE ENCASEMENT, SLEEVING AND TUNNELS</b> May be in different forms: steel, poured concrete, box sections, slabs.</p>
	<p><b>CHANGE INDICATOR ARROW</b> Indicates a change in pipe type or size. e.g. 150mm diameter PVC to 150mm diameter asbestos cement (AC).</p>
	<p><b>PIPE OVERPASS</b> The overpass symbol indicates the shallower of the two pipes.</p>
	<p><b>VALVES</b> Many different valve types are in use. Valve may be in a pit or have a visible valve cover. There may be no surface indication.</p> <p>Valves may be shallower than the main or offset from it. e.g. A scour valve (SC) may have a pipe coming away from main pipeline on the opposite side to that indicated on the plan.</p>



**Board:** 1/24/2022  
**Mapbook No:** 227-10000  
**Print Date:** 1/27/2022 **Page:** 1 of 6



**WARNING - CRITICAL PIPELINE**  
 Refer to Information Structure Diagrams  
 Prevalence and Legend for details




The Water Corporation has issued this map to the responsibility of the user. The user is responsible for the accuracy of the information shown on this map. The user is responsible for the accuracy of the information shown on this map. The user is responsible for the accuracy of the information shown on this map.



Scale: 1"=500'  
 Custom Point: 1943449, -91.9441"  
 Sequence No: 22732333  
 PWD Date: 1/17/2023 Page: 2 of 6



**WARNING - CRITICAL PIPELINE**  
 Refer to Information Graphics Database  
 Provisions and Legend for details




This Water Corporation has done due diligence in the preparation of this map. It is not responsible for any errors or omissions. The user assumes all responsibility for the use of this map. The user agrees to indemnify and hold the Water Corporation harmless from any and all claims, damages, costs, and expenses, including reasonable attorneys' fees, arising from the use of this map. The Water Corporation is not liable for any damages, including consequential damages, arising from the use of this map. The Water Corporation is not responsible for any errors or omissions in this map. The user assumes all responsibility for the use of this map.





**WARNING - CRITICAL PIPELINE**  
 Refer to Information Brochure (Damage Prevention) and Legend for details



This Water Conservation Plan is a design document that is the property of the City of Pickle. It is provided to you for your information and use only. It is not to be used for any other purpose without the written consent of the City of Pickle. The City of Pickle is not responsible for any errors or omissions in this plan. The City of Pickle is not responsible for any damage to property or persons resulting from the use of this plan. The City of Pickle is not responsible for any damage to property or persons resulting from the use of this plan. The City of Pickle is not responsible for any damage to property or persons resulting from the use of this plan.






Station: 11+000  
 Center Point: 11181000, -81.1241°  
 Elevation: 2271.0000  
 Plot Date: 7/20/2025 Page: 5 of 8



**WARNING - CRITICAL PIPELINE**  
 Refer to Excavation Structure Damage  
 Prevention and Legend for details



The Water Corporation has taken every care in the preparation of this map but does not accept responsibility for any errors or omissions. The user of this map is advised that it is not intended for use as a substitute for a survey or other professional engineering or architectural drawing. The Water Corporation is not liable for any damages, including consequential damages, arising from the use of this map.



Scale: 1"=100'  
 Date: 1/17/2023  
 Project: 170700000 Page 8 of 8



**WARNING - CRITICAL PIPELINE**  
 Refer to Information Brochure Damage Prevention and Layouts for details






Index Page

Scale: 1:4000

Map Date: 1/27/2023


Page 1 of 5



The Water Department has every effort to ensure the accuracy of this map, but cannot be held responsible for any errors or omissions. This map may be used for informational purposes only and should not be used for legal or financial purposes. The Water Department is not responsible for any damages or losses resulting from the use of this map. The Water Department is not responsible for any damages or losses resulting from the use of this map.




Scale: 1" = 100'  
 Contour Points: 14' ELEVATION, 34' ELEVATION  
 Sequence No: 2874 (2020)  
 Date: 07/20/2020  
 Project: 2020



The Water Corporation has shown this map in the jurisdiction of the Town of Pickle. It is not intended to be used for any other purpose. The Water Corporation is not responsible for any errors or omissions in this map. The Water Corporation is not responsible for any damages or liabilities arising from the use of this map. The Water Corporation is not responsible for any claims or lawsuits arising from the use of this map. The Water Corporation is not responsible for any claims or lawsuits arising from the use of this map.




Scale: 1"=100' City of Canton Public Utilities, 3/18/2011  
 Surveyed: May 22, 1999  
 Field Date: 7/20/2009 Page: 3 of 4



The Water Department has shown the location of all valves, hydrants and other appurtenances for the water system. The location of all valves, hydrants and other appurtenances for the water system is shown on this map. The location of all valves, hydrants and other appurtenances for the water system is shown on this map. The location of all valves, hydrants and other appurtenances for the water system is shown on this map.




Scale: 1:1000  
 Cadastre Point: (462419, 314607)  
 Date: 2023-08-28  
 Page: 4 of 6




This document is a preliminary plan and is not intended to be used as a final plan. It is subject to change without notice. The user of this document is advised to consult with the appropriate authorities for the most current information. The user of this document is advised to consult with the appropriate authorities for the most current information.





The information shown on this map was derived from the City of Dallas Utility Information System (UIS) as of the date of the last data update. The City of Dallas is not responsible for any errors or omissions on this map. The City of Dallas is not responsible for any damages or liabilities arising from the use of this map. The City of Dallas is not responsible for any damages or liabilities arising from the use of this map.



The Water Corporation has taken every care to ensure the accuracy of this map. However, the Water Corporation does not warrant the accuracy of this map. The Water Corporation is not responsible for any errors or omissions on this map. The Water Corporation is not responsible for any damage to property or injury to persons resulting from the use of this map. The Water Corporation is not responsible for any loss of data or information resulting from the use of this map. The Water Corporation is not responsible for any other consequences of the use of this map.



Scale: 1:8000  
 Map Date: 4/20/2022  
 Page 1 of 5



Index Page

Page 4

Page 2

Page 3


Page 6

Page 5

This Water Department map is for informational purposes only. It is not intended to be used as a legal document. The map is not a warranty of any kind. The map is not a guarantee of any kind. The map is not a representation of any kind. The map is not a statement of any kind. The map is not a declaration of any kind. The map is not a promise of any kind. The map is not a contract of any kind. The map is not a deed of any kind. The map is not a will of any kind. The map is not a power of attorney of any kind. The map is not a trust agreement of any kind. The map is not a lease agreement of any kind. The map is not a license agreement of any kind. The map is not a service agreement of any kind. The map is not a partnership agreement of any kind. The map is not a joint venture agreement of any kind. The map is not a joint tenancy agreement of any kind. The map is not a tenancy in common agreement of any kind. The map is not a tenancy at will agreement of any kind. The map is not a tenancy at sufferance agreement of any kind. The map is not a tenancy by estoppel agreement of any kind. The map is not a tenancy by the entirety agreement of any kind. The map is not a tenancy in fee simple agreement of any kind. The map is not a tenancy in fee simple subject to a condition subsequent agreement of any kind. The map is not a tenancy in fee simple subject to a condition precedent agreement of any kind. The map is not a tenancy in fee simple subject to a right of reverter agreement of any kind. The map is not a tenancy in fee simple subject to a right of redemption agreement of any kind. The map is not a tenancy in fee simple subject to a right of first refusal agreement of any kind. The map is not a tenancy in fee simple subject to a right of first offer agreement of any kind. The map is not a tenancy in fee simple subject to a right of first refusal agreement of any kind. The map is not a tenancy in fee simple subject to a right of first offer agreement of any kind. The map is not a tenancy in fee simple subject to a right of first refusal agreement of any kind. The map is not a tenancy in fee simple subject to a right of first offer agreement of any kind.




Scale: 1"=100'  
 Date: 11/20/2013  
 County: Pickle  
 Project: 101-22-101  
 Sheet: 5 of 8



101-22-101  
 101-22-102  
 101-22-103  
 101-22-104  
 101-22-105  
 101-22-106  
 101-22-107  
 101-22-108  
 101-22-109  
 101-22-110  
 101-22-111  
 101-22-112  
 101-22-113  
 101-22-114  
 101-22-115  
 101-22-116  
 101-22-117  
 101-22-118  
 101-22-119  
 101-22-120  
 101-22-121  
 101-22-122  
 101-22-123  
 101-22-124  
 101-22-125  
 101-22-126  
 101-22-127  
 101-22-128  
 101-22-129  
 101-22-130  
 101-22-131  
 101-22-132  
 101-22-133  
 101-22-134  
 101-22-135  
 101-22-136  
 101-22-137  
 101-22-138  
 101-22-139  
 101-22-140  
 101-22-141  
 101-22-142  
 101-22-143  
 101-22-144  
 101-22-145  
 101-22-146  
 101-22-147  
 101-22-148  
 101-22-149  
 101-22-150  
 101-22-151  
 101-22-152  
 101-22-153  
 101-22-154  
 101-22-155  
 101-22-156  
 101-22-157  
 101-22-158  
 101-22-159  
 101-22-160  
 101-22-161  
 101-22-162  
 101-22-163  
 101-22-164  
 101-22-165  
 101-22-166  
 101-22-167  
 101-22-168  
 101-22-169  
 101-22-170  
 101-22-171  
 101-22-172  
 101-22-173  
 101-22-174  
 101-22-175  
 101-22-176  
 101-22-177  
 101-22-178  
 101-22-179  
 101-22-180  
 101-22-181  
 101-22-182  
 101-22-183  
 101-22-184  
 101-22-185  
 101-22-186  
 101-22-187  
 101-22-188  
 101-22-189  
 101-22-190  
 101-22-191  
 101-22-192  
 101-22-193  
 101-22-194  
 101-22-195  
 101-22-196  
 101-22-197  
 101-22-198  
 101-22-199  
 101-22-200



Scale: 1" = 100'  
 Drawing No: 2271-0200  
 Project: STANWOOD SUBDIVISION







Scale: 1:1,000  
 Drawing No: 2871-02-00  
 Plot Date: 07/27/2023 Page 3 of 8



The Water Corporation does not take any responsibility for the accuracy of the information shown on this map. The Water Corporation is not liable for any loss or damage arising from the use of this map. The Water Corporation is not responsible for any errors or omissions on this map. The Water Corporation is not responsible for any changes to the information shown on this map. The Water Corporation is not responsible for any legal consequences arising from the use of this map.



Scale: 1"=100'  
 Date: 11/15/2023  
 Project: 150700000  
 Page: 8 of 8



The Water Department has taken the information of this map as accurate to the best of its knowledge. It is not responsible for any errors or omissions. The user of this map is advised to verify the information shown on this map with the appropriate authorities. The Water Department is not responsible for any errors or omissions. The user of this map is advised to verify the information shown on this map with the appropriate authorities.